



AD NO. \_\_\_\_\_  
DTC PROJECT NO. 8-CO-160-UXO-021  
REPORT NO. ATC-9106



STANDARDIZED

UXO TECHNOLOGY DEMONSTRATION SITE

WOODS SCORING RECORD NO. 381


SITE LOCATION:  
U.S. ARMY ABERDEEN PROVING GROUND

DEMONSTRATOR:  
GEOPHYSICAL TECHNOLOGY LIMITED (G-TEK)  
UNIT 3, NO. 10, HUDSON ROAD  
ALBION, AUSTRALIA 4010

TECHNOLOGY TYPE/PLATFORM:  
SUB-AUDIO MAGNETICS (SAM)/SLING  
DUAL MODE

PREPARED BY:  
U.S. ARMY ABERDEEN TEST CENTER  
ABERDEEN PROVING GROUND, MD 21005-5059

OCTOBER 2005



Prepared for:  
U.S. ARMY ENVIRONMENTAL CENTER  
ABERDEEN PROVING GROUND, MD 21010-5401

U.S. ARMY DEVELOPMENTAL TEST COMMAND  
ABERDEEN PROVING GROUND, MD 21005-5055

DISTRIBUTION UNLIMITED, SEPTEMBER 2005.

### DISPOSITION INSTRUCTIONS

Destroy this document when no longer needed. Do not return to the originator.

The use of trade names in this document does not constitute an official endorsement or approval of the use of such commercial hardware or software. This document may not be cited for purposes of advertisement.

| REPORT DOCUMENTATION PAGE  |                         |   |   | Form Approved<br>OMB No. 0704-0188 |  |
|--|-------------------------|---|---|------------------------------------|--|
| <p>The public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing the burden, to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports (0704-0188), 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.</p> <p><b>PLEASE DO NOT RETURN YOUR FORM TO THE ABOVE ADDRESS.</b></p> |                         |   |   |                                    |  |
| 1. REPORT DATE (DD-MM-YYYY)<br>October 2005  | 2. REPORT TYPE<br>Final | 3. DATES COVERED (From - To)<br>28 and 29 May and 1 June 2004 |   |                                    |  |
| <b>4. TITLE AND SUBTITLE</b><br>STANDARDIZED UXO TECHNOLOGY DEMONSTRATION SITE<br>WOODS SCORING RECORD NO. 381 (GEOPHYSICAL TECHNOLOGY<br>LIMITED)   |                         |   | 5a. CONTRACT NUMBER   |                                    |  |
|  |                         |   | 5b. GRANT NUMBER  |                                    |  |
|  |                         |   | 5c. PROGRAM ELEMENT NUMBER                                      |                                    |  |
| <b>6. AUTHOR(S)</b><br>Overbay, Larry; Robitaille, George<br>The Standardized UXO Technology Demonstration Site Scoring Committee  |                         |   | 5d. PROJECT NUMBER<br>8-CO-160-UXO-021                          |                                    |  |
|  |                         |   | 5e. TASK NUMBER   |                                    |  |
|  |                         |   | 5f. WORK UNIT NUMBER  |                                    |  |
| <b>7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES)</b><br>Commander<br>U.S. Army Aberdeen Test Center<br>ATTN: CSTE-DTC-AT-SL-E<br>Aberdeen Proving Ground, MD 21005-5059   |                         |   | <b>8. PERFORMING ORGANIZATION REPORT NUMBER</b><br>ATC-9106     |                                    |  |
| <b>9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)</b><br>Commander<br>U.S. Army Environmental Center<br>ATTN: SFIM-AEC-ATT<br>Aberdeen Proving Ground, MD 21005-5401  |                         |   | <b>10. SPONSOR/MONITOR'S ACRONYM(S)</b>                         |                                    |  |
|  |                         |   | <b>11. SPONSOR/MONITOR'S REPORT NUMBER(S)</b><br>Same as Item 8 |                                    |  |
| <b>12. DISTRIBUTION/AVAILABILITY STATEMENT</b><br>Distribution unlimited.  |                         |   |   |                                    |  |
| <b>13. SUPPLEMENTARY NOTES</b>   |                         |   |   |                                    |  |
| <b>14. ABSTRACT</b><br>This scoring record documents the efforts of Geophysical Technology Limited (G-TEK) to detect and discriminate inert unexploded ordnance (UXO) utilizing the APG Standardized UXO Technology Demonstration Site Woods. Scoring Records have been coordinated by Larry Overbay and the Standardized UXO Technology Demonstration Site Scoring Committee. Organizations on the committee include, the U.S. Army Corps of Engineers, the Environmental Security Technology Certification Program, the Strategic Environmental Research and Development Program, the Institute for Defense Analysis, the U.S. Army Environmental Center, and the U.S. Army Aberdeen Test Center.  |                         |   |   |                                    |  |
| <b>15. SUBJECT TERMS</b><br>G-TEK, UXO Standardized Technology Demonstration Site Program, Woods, Sub-Audio Magnetics (SAM)/Sling  |                         |   |   |                                    |  |
| <b>16. SECURITY CLASSIFICATION OF:</b><br>a. REPORT Unclassified   |                         |   | <b>17. LIMITATION OF ABSTRACT</b><br>UL                         | <b>18. NUMBER OF PAGES</b>         | 19a. NAME OF RESPONSIBLE PERSON<br>19b. TELEPHONE NUMBER (Include area code) |

## **ACKNOWLEDGEMENTS**

### **Authors:**

Larry Overbay Jr.

Matthew Boutin

Military Environmental Technology Demonstration Center (METDC)  
U.S. Army Aberdeen Test Center (ATC)  
U.S. Army Aberdeen Proving Ground (APG)

Rick Fling

Aberdeen Test and Support Services (ATSS)  
Sverdrup Technology, Inc.  
U.S. Army Aberdeen Proving Ground (APG)

Christina McClung

Aberdeen Data Services Team (ADST)

Tri-S, Inc.

U.S. Army Aberdeen Proving Ground (APG)

### **Contributor:**

George Robitaille

U.S. Army Environmental Center (AEC)  
U.S. Army Aberdeen Proving Ground (APG)

## TABLE OF CONTENTS

|  | <u>PAGE</u> |
|--|-------------|
| ACKNOWLEDGMENTS .....  | i           |
| <br><b><u>SECTION 1. GENERAL INFORMATION</u></b>                         |             |
| 1.1 BACKGROUND .....   | 1           |
| 1.2 SCORING OBJECTIVES .....   | 1           |
| 1.2.1 Scoring Methodology .....  | 1           |
| 1.2.2 Scoring Factors .....  | 2           |
| 1.3 STANDARD AND NONSTANDARD INERT ORDNANCE TARGETS .....                | 3           |
| <br><b><u>SECTION 2. DEMONSTRATION</u></b>                               |             |
| 2.1 DEMONSTRATOR INFORMATION .....                                       | 5           |
| 2.1.1 Demonstrator Point of Contact (POC) and Address .....              | 5           |
| 2.1.2 System Description .....   | 5           |
| 2.1.3 Data Processing Description .....                                  | 7           |
| 2.1.4 Data Submission Format .....                                       | 7           |
| 2.1.5 Demonstrator Quality Assurance (QA) and Quality Control (QC) ..... | 7           |
| 2.1.6 Additional Records .....   | 8           |
| 2.2 APG SITE INFORMATION .....   | 8           |
| 2.2.1 Location .....   | 8           |
| 2.2.2 Soil Type .....  | 8           |
| 2.2.3 Test Areas .....   | 8           |
| <br><b><u>SECTION 3. FIELD DATA</u></b>                                  |             |
| 3.1 DATE OF FIELD ACTIVITIES .....                                       | 11          |
| 3.2 AREAS TESTED/NUMBER OF HOURS .....                                   | 11          |
| 3.3 TEST CONDITIONS .....  | 11          |
| 3.3.1 Weather Conditions .....   | 11          |
| 3.3.2 Field Conditions .....   | 11          |
| 3.3.3 Soil Moisture .....  | 11          |
| 3.4 FIELD ACTIVITIES .....   | 12          |
| 3.4.1 Setup/Mobilization .....   | 12          |
| 3.4.2 Calibration .....  | 12          |
| 3.4.3 Downtime Occasions .....   | 12          |
| 3.4.4 Data Collection .....  | 12          |
| 3.4.5 Demobilization .....   | 12          |
| 3.5 PROCESSING TIME .....  | 13          |
| 3.6 DEMONSTRATOR'S FIELD PERSONNEL .....                                 | 13          |
| 3.7 DEMONSTRATOR'S FIELD SURVEYING METHOD .....                          | 13          |
| 3.8 SUMMARY OF DAILY LOGS .....  | 13          |

## **SECTION 4. TECHNICAL PERFORMANCE RESULTS**

|  | <b>PAGE</b> |
|--|-------------|
| 4.1 ROC CURVES USING ALL ORDNANCE CATEGORIES .....             | 15          |
| 4.2 ROC CURVES USING ORDNANCE LARGER THAN 20 MM .....          | 17          |
| 4.3 PERFORMANCE SUMMARIES .....                                | 19          |
| 4.4 EFFICIENCY, REJECTION RATES, AND TYPE CLASSIFICATION ..... | 21          |
| 4.5 LOCATION ACCURACY .....                                    | 22          |

## **SECTION 5. ON-SITE LABOR COSTS**

## **SECTION 6. COMPARISON OF RESULTS TO OPEN FIELD DEMONSTRATION**

|  |    |
|--|----|
| 6.1 SUMMARY OF RESULTS FROM OPEN FIELD DEMONSTRATION .....             | 25 |
| 6.2 COMPARISON OF ROC CURVES USING ALL ORDNANCE<br>CATEGORIES .....    | 25 |
| 6.3 COMPARISON OF ROC CURVES USING ORDNANCE LARGER THAN<br>20 MM ..... | 27 |
| 6.4 STATISTICAL COMPARISONS .....                                      | 28 |

## **SECTION 7. APPENDIXES**

|                               |     |
|-------------------------------|-----|
| A TERMS AND DEFINITIONS ..... | A-1 |
| B DAILY WEATHER LOGS .....    | B-1 |
| C SOIL MOISTURE .....         | C-1 |
| D DAILY ACTIVITY LOGS .....   | D-1 |
| E REFERENCES .....            | E-1 |
| F ABBREVIATIONS .....         | F-1 |
| G DISTRIBUTION LIST .....     | G-1 |

## **SECTION 1. GENERAL INFORMATION**

### **1.1 BACKGROUND**

Technologies under development for the detection and discrimination of unexploded ordnance (UXO) require testing so that their performance can be characterized. To that end, Standardized Test Sites have been developed at Aberdeen Proving Ground (APG), Maryland and U.S. Army Yuma Proving Ground (YPG), Arizona. These test sites provide a diversity of geology, climate, terrain, and weather as well as diversity in ordnance and clutter. Testing at these sites is independently administered and analyzed by the government for the purposes of characterizing technologies, tracking performance with system development, comparing performance of different systems, and comparing performance in different environments.

The Standardized UXO Technology Demonstration Site Program is a multi-agency program spearheaded by the U.S. Army Environmental Center (AEC). The U.S. Army Aberdeen Test Center (ATC) and the U.S. Army Corps of Engineers Engineering Research and Development Center (ERDC) provide programmatic support. The program is being funded and supported by the Environmental Security Technology Certification Program (ESTCP), the Strategic Environmental Research and Development Program (SERDP) and the Army Environmental Quality Technology Program (EQT).

### **1.2 SCORING OBJECTIVES**

The objective in the Standardized UXO Technology Demonstration Site Program is to evaluate the detection and discrimination capabilities of a given technology under various field and soil conditions. Inert munitions and clutter items are positioned in various orientations and depths in the ground.

The evaluation objectives are as follows:

- a. To determine detection and discrimination effectiveness under realistic scenarios that vary targets, geology, clutter, topography, and vegetation.
- b. To determine cost, time, and manpower requirements to operate the technology.
- c. To determine demonstrator's ability to analyze survey data in a timely manner and provide prioritized "Target Lists" with associated confidence levels.
- d. To provide independent site management to enable the collection of high quality, ground-truth, geo-referenced data for post-demonstration analysis.

#### **1.2.1 Scoring Methodology**

- a. The scoring of the demonstrator's performance is conducted in two stages. These two stages are termed the RESPONSE STAGE and DISCRIMINATION STAGE. For both stages, the probability of detection ( $P_d$ ) and the false alarms are reported as receiver-operating

characteristic (ROC) curves. False alarms are divided into those anomalies that correspond to emplaced clutter items, measuring the probability of false positive ( $P_{fp}$ ), and those that do not correspond to any known item, termed background alarms.

b. The RESPONSE STAGE scoring evaluates the ability of the system to detect emplaced targets without regard to ability to discriminate ordnance from other anomalies. For the blind grid RESPONSE STAGE, the demonstrator provides the scoring committee with a target response from each and every grid square along with a noise level below which target responses are deemed insufficient to warrant further investigation. This list is generated with minimal processing and, since a value is provided for every grid square, will include signals both above and below the system noise level.

c. The DISCRIMINATION STAGE evaluates the demonstrator's ability to correctly identify ordnance as such and to reject clutter. For the blind grid DISCRIMINATION STAGE, the demonstrator provides the scoring committee with the output of the algorithms applied in the discrimination-stage processing for each grid square. The values in this list are prioritized based on the demonstrator's determination that a grid square is likely to contain ordnance. Thus, higher output values are indicative of higher confidence that an ordnance item is present at the specified location. For digital signal processing, priority ranking is based on algorithm output. For other discrimination approaches, priority ranking is based on human (subjective) judgment. The demonstrator also specifies the threshold in the prioritized ranking that provides optimum performance, (i.e. that is expected to retain all detected ordnance and rejects the maximum amount of clutter).

d. The demonstrator is also scored on EFFICIENCY and REJECTION RATIO, which measures the effectiveness of the discrimination stage processing. The goal of discrimination is to retain the greatest number of ordnance detections from the anomaly list, while rejecting the maximum number of anomalies arising from non-ordnance items. EFFICIENCY measures the fraction of detected ordnance retained after discrimination, while the REJECTION RATIO measures the fraction of false alarms rejected. Both measures are defined relative to performance at the demonstrator-supplied level below which all responses are considered noise, i.e., the maximum ordnance detectable by the sensor and its accompanying false positive rate or background alarm rate.

e. Based on configuration of the ground truth at the standardized sites and the defined scoring methodology, there exists the possibility of having anomalies within overlapping halos and/or multiple anomalies within halos. In these cases, the following scoring logic is implemented:

(1) In situations where multiple anomalies exist within a single  $R_{halo}$ , the anomaly with the strongest response or highest ranking will be assigned to that particular ground truth item.

(2) For overlapping  $R_{halo}$  situations, ordnance has precedence over clutter. The anomaly with the strongest response or highest ranking that is closest to the center of a particular ground truth item gets assigned to that item. Remaining anomalies are retained until all matching is complete.

(3) Anomalies located within any  $R_{\text{halo}}$  that do not get associated with a particular ground truth item are thrown out and are not considered in the analysis.

f. All scoring factors are generated utilizing the Standardized UXO Probability and Plot Program, version 3.1.1.

### **1.2.2 Scoring Factors**

Factors to be measured and evaluated as part of this demonstration include:

a. Response Stage ROC curves:

- (1) Probability of Detection ( $P_d^{\text{res}}$ ).
- (2) Probability of False Positive ( $P_{fp}^{\text{res}}$ ).
- (3) Background Alarm Rate ( $\text{BAR}^{\text{res}}$ ) or Probability of Background Alarm ( $P_{BA}^{\text{res}}$ ).

b. Discrimination Stage ROC curves:

- (1) Probability of Detection ( $P_d^{\text{disc}}$ ).
- (2) Probability of False Positive ( $P_{fp}^{\text{disc}}$ ).
- (3) Background Alarm Rate ( $\text{BAR}^{\text{disc}}$ ) or Probability of Background Alarm ( $P_{BA}^{\text{disc}}$ ).

c. Metrics:

- (1) Efficiency (E).
- (2) False Positive Rejection Rate ( $R_{fp}$ ).
- (3) Background Alarm Rejection Rate ( $R_{BA}$ ).

d. Other:

- (1) Probability of Detection by Size and Depth.
- (2) Classification by type (i.e., 20-, 40-, 105-mm, etc.).
- (3) Location accuracy.
- (4) Equipment setup, calibration time and corresponding man-hour requirements.
- (5) Survey time and corresponding man-hour requirements.

- (6) Reacquisition/resurvey time and man-hour requirements (if any).
- (7) Downtime due to system malfunctions and maintenance requirements.

### **1.3 STANDARD AND NONSTANDARD INERT ORDNANCE TARGETS**

The standard and nonstandard ordnance items emplaced in the test areas are listed in Table 1. Standardized targets are members of a set of specific ordnance items that have identical properties to all other items in the set (caliber, configuration, size, weight, aspect ratio, material, filler, magnetic remanence, and nomenclature). Nonstandard targets are inert ordnance items having properties that differ from those in the set of standardized targets.

**TABLE 1. INERT ORDNANCE TARGETS**

| <b>Standard Type</b>         | <b>Nonstandard (NS)</b> |
|------------------------------|-------------------------|
| 20-mm Projectile M55         | 20-mm Projectile M55    |
|                              | 20-mm Projectile M97    |
| 40-mm Grenades M385          | 40-mm Grenades M385     |
| 40-mm Projectile MKII Bodies | 40-mm Projectile M813   |
| BDU-28 Submunition           |                         |
| BLU-26 Submunition           |                         |
| M42 Submunition              |                         |
| 57-mm Projectile APC M86     |                         |
| 60-mm Mortar M49A3           | 60-mm Mortar (JPG)      |
|                              | 60-mm Mortar M49        |
| 2.75-inch Rocket M230        | 2.75-inch Rocket M230   |
|                              | 2.75-inch Rocket XM229  |
| MK 118 ROCKEYE               |                         |
| 81-mm Mortar M374            | 81-mm Mortar (JPG)      |
|                              | 81-mm Mortar M374       |
| 105-mm Heat Rounds M456      |                         |
| 105-mm Projectile M60        | 105-mm Projectile M60   |
| 155-mm Projectile M483A1     | 155-mm Projectile M483A |
|                              | 500-lb Bomb             |

JPG = Jefferson Proving Ground

HEAT = high-explosive, antitank

## **SECTION 2. DEMONSTRATION**

### **2.1 DEMONSTRATOR INFORMATION**

#### **2.1.1 Demonstrator Point of Contact (POC) and Address**

POC: Dr. John M. Stanley  
256 895 1625 (+61 7 3862 2588)

Address: Geophysical Technology Limited (G-TEK)  
Unit 3, No. 10, Hudson Road  
Albion, Australia 4010

#### **2.1.2 System Description (provided by demonstrator)**

Sub-Audio Magnetics (SAM)/Sling dual mode (fig. 1) is a method by which a total field-magnetometer sampling at a very high rate may be used to simultaneously acquire both Total Magnetic Intensity (TMI) and Total Field Electromagnetic Induction (TFEMI) data. The SAM system consists of the following components:



Figure 1. Demonstrator's system, SAM/Sling dual mode.

### Magnetometer:

The SAM capable TM-6 magnetometer to be used has been developed and built by G-TEK. Its salient features include:

1. Accepts Larmor signal input from a hand-held array of four optically pumped magnetic sensors.
2. Simultaneously acquires magnetic field measurements from each sensor at selectable rates up to 4,800 per second.
3. Acquires measurements at precise intervals of time in synchronization with Global Positioning System (GPS) time.
4. The root-mean-square (RMS) noise floor for each measurement sample rate typically lies between 1 nT at 10,000 per second to 1 pT at 100 per second when plotted on a logarithmic abscissa. In this program we propose sampling at 4,800 per second where the noise is approximately 0.2 nT, reducible in late-time by the averaging of consecutive samples.
5. Accepts position and time information including 1-pps strobe from Differential Global Positioning System (DGPS).
6. Magnetometer, DGPS, and batteries to power a quad-sensor array for 2.5 hours are carried in a backpack weighing about 8 kg.
7. Graphic user interface implemented on a Pocket PC.

### Electromagnetic Transmitter:

An eight-turn wire loop is laid out along a meandering path that surrounds the grid area to be surveyed (typically 33 by 33 m). A Zonge GGT-10 current transmitter energizes this loop with a bipolar, 12- to 20-amp square wave current usually of 50 percent duty cycle and 15 Hz frequency. The transmitter and receiving magnetometer are precisely synchronized using GPS time.

### Data Positioning Systems:

The TM-6 magnetometer system has been designed to interface with a variety of positioning devices as different application localities have different characteristics and requirements. There is a requirement when using the magnetometer for SAM applications that access is available to GPS time at least once every 30 minutes in order to maintain precise clock synchronization. However, this time signal may be obtainable in conditions such as wooded areas where DGPS positional accuracy is not satisfactory. In such situations, cotton thread based odometer system developed by G-TEK and used for more than 25 years provides a good alternative. However, emerging new technologies such as the Robotic Total Station (RTS) have been allowed for in the design of the magnetometer. At the APG site it is proposed that both the odometer and RTS will be used in the forested area for the purpose of evaluating their relative performance.

### **2.1.3 Data Processing Description (provided by demonstrator)**

The raw TM-6 data is processed using a proprietary software package referred to as MagPi which performs all preprocessing procedures including separation of the magnetic TMI and electromagnetic (EM) data TFEMI sets, waveform stacking, removal of unwanted frequency components such as 60 Hz noise, EM decay curve integration, decimation, merging of DGPS time/position, and low-pass filtering. The MagPi output is usually in the form of Excel style comma separated values (csv) files (time decays) or Geosoft XYZ files. The Geosoft Mapping Package is used for data management, gridding, map creation and display, and other specialized filtering. Two proprietary products referred to as MagSys (G-TEK) and UXOlab (University of British Columbia) are used for additional interpretation of the gridded data, in order to provide automatic anomaly picking, calculation of certain anomaly parameters, forward modeling, and inversion. The SAM electromagnetic interface (EMI) method provides two complementary data sets (TMI and TFEMI) that are perfectly georeferenced because the same sensor is used to acquire both data types simultaneously. For these technology demonstrations the individual data sets will be processed separately to the point of producing the XYZ files, but the results will be presented as a single joint interpretation, using selected information from each data set combined in a logical and optimal manner. In the specific case of small ordnance items such as grenades and submunitions, the TFEMI response is likely to be below the noise floor with the TFEMI, in which case the interpretation will be based on the TMI alone.

### **2.1.4 Data Submission Format**

Data were submitted for scoring in accordance with data submission protocols outlined in the Standardized UXO Technology Demonstration Site Handbook. These submitted data are not included in this report in order to protect ground truth information.

### **2.1.5 Demonstrator Quality Assurance (QA) and Quality Control (QC) (provided by demonstrator)**

Overview of QC. Prior to the commencement of survey each day, a system integrity test procedure will be conducted exceeding the requirements of DID 005 05.02. This procedure, described in Appendix D will include:

1. A test for sensor warm-up and signal health.
2. The testing of personnel for demagnetization and metal-free clothing.
3. A cable vibration test in conjunction with in-built system integrity checks.
4. A sensor array position check.
5. Acquiring a DGPS latency, sensor offset, and data integrity record using a six-line test performed over the energized wire loop.
6. A heading and azimuthal test.

7. A repeat line test.
8. Occupying a known position and recording its measured position.

Overview of QA. The most important aspect of quality assurance for this demonstration is that all measurements are accurately recorded and well documented. Detailed signed and dated field notes will accompany all digital data files. The QA officer (JMS) will independently evaluate the calibration data files and the demonstration survey data files. Data not compliant with the survey specifications will be reacquired.

### **2.1.6 Additional Records**

The following record(s) by this vendor can be accessed via the Internet as MicroSoft Word documents at [www.uxotestsites.org](http://www.uxotestsites.org). The Blind Grid counterpart to this report is Scoring Record No. 281, the Open Field, Scoring Record No. 379, and the Woods, Scoring Record No. 381.

## **2.2 APG SITE INFORMATION**

### **2.2.1 Location**

The APG Standardized Test Site is located within a secured range area of the Aberdeen Area. The Aberdeen Area of APG is located approximately 30 miles northeast of Baltimore at the northern end of the Chesapeake Bay. The Standardized Test Site encompasses 17 acres of upland and lowland flats, woods, and wetlands.

### **2.2.2 Soil Type**

According to the soils survey conducted for the entire area of APG in 1998, the test site consists primarily of Elkton Series type soil (ref 2). The Elkton Series consist of very deep, slowly permeable, poorly drained soils. These soils formed in silty aeolian sediments and the underlying loamy alluvial and marine sediments. They are on upland and lowland flats and in depressions of the Mid-Atlantic Coastal Plain. Slopes range from 0 to 2 percent.

ERDC conducted a site-specific analysis in May of 2002 (ref 3). The results basically matched the soil survey mentioned above. Seventy percent of the samples taken were classified as silty loam. The majority (77 percent) of the soil samples had a measured water content between 15- and 30-percent with the water content decreasing slightly with depth.

For more details concerning the soil properties at the APG test site, go to [www.uxotestsites.org](http://www.uxotestsites.org) on the web to view the entire soils description report.

### **2.2.3 Test Areas**

A description of the test site areas at APG is included in Table 2.

**TABLE 2. TEST SITE AREAS**

| <b>Area</b>      | <b>Description</b>   |
|------------------|--|
| Calibration Grid | Contains 14 standard ordnance items buried in six positions at various angles and depths to allow demonstrator to calibrate their equipment.   |
| Blind Test Grid  | Contains 400 grid cells in a 0.2-hectare (0.5 acre) site. The center of each grid cell contains ordnance, clutter or nothing.  |
| Open Field       | A 4-hectare (10-acre) site containing open areas, dips, ruts and obstructions that challenge platform systems or hand held detectors. The challenges include a gravel road, wet areas and trees. The vegetation height varies from 15 to 25 cm.              |
| Moguls           | 1.30-acre area consisting of two areas (the rectangular or driving portion of the course and the triangular section with more difficult, non-drivable terrain). A series of craters (as deep as 0.91m) and mounds (as high as 0.91m) encompass this section. |

### **SECTION 3. FIELD DATA**

#### **3.1 DATE OF FIELD ACTIVITIES (28 and 29 May and 1 June 2004)**

#### **3.2 AREAS TESTED/NUMBER OF HOURS**

Areas tested and total number of hours operated at each site are summarized in Table 3.

**TABLE 3. AREAS TESTED AND NUMBER OF HOURS**

| <b>Area</b>       | <b>Number of Hours</b> |
|-------------------|------------------------|
| Calibration Lanes | 2.66                   |
| Woods             | 23.92                  |

#### **3.3 TEST CONDITIONS**

##### **3.3.1 Weather Conditions**

An APG weather station located approximately one mile west of the test site was used to record average temperature and precipitation on a half hour basis for each day of operation. The temperatures listed in Table 4 represent the average temperature during field operations from 0700 to 1700 hours while precipitation data represents a daily total amount of rainfall. Hourly weather logs used to generate this summary are provided in Appendix B.

**TABLE 4. TEMPERATURE/PRECIPITATION DATA SUMMARY**

| <b>Date, 2004</b> | <b>Average Temperature, °F</b> | <b>Total Daily Precipitation, in.</b> |
|-------------------|--------------------------------|---------------------------------------|
| 28 May            | 76.62                          | 0.01                                  |
| 29 May            | 66.15                          | 0.00                                  |
| 01 June           | 72.01                          | 0.19                                  |

##### **3.3.2 Field Conditions**

G-TEK surveyed the Woods 28 and 29 May and 1 June 2004. The Woods had several muddy areas due to rain prior and during testing.

##### **3.3.3 Soil Moisture**

Three soil probes were placed at various locations within the site to capture soil moisture data: Blind Grid, Calibration, Mogul, and Open Field areas. Measurements were collected in percent moisture and were taken twice daily (morning and afternoon) from five different soil depths (1 to 6 in., 6 to 12 in., 12 to 24 in., 24 to 36 in., and 36 to 48 in.) from each probe. Soil moisture logs are included in Appendix C.

## **3.4 FIELD ACTIVITIES**

### **3.4.1 Setup/Mobilization**

These activities included initial mobilization and daily equipment preparation and break down. A five-person crew took 5 hours to perform the initial setup and mobilization. There was 10 hours and 15 minutes of daily equipment preparation and end of the day equipment break down lasted 50 minutes.

### **3.4.2 Calibration**

G-TEK spent a total of 2 hours and 40 minutes in the calibration lanes, of which 1 hour and 40 minutes was spent collecting data.

### **3.4.3 Downtime Occasions**

Occasions of downtime are grouped into five categories: equipment/data checks or equipment maintenance, equipment failure and repair, weather, Demonstration Site issues, or breaks/lunch. All downtime is included for the purposes of calculating labor costs (section 5) except for downtime due to Demonstration Site issues. Demonstration Site issues, while noted in the Daily Log, are considered nonchargeable downtime for the purposes of calculating labor costs and are not discussed. Breaks and lunches are discussed in this section and billed to the total Site Survey area.

**3.4.3.1 Equipment/data checks, maintenance.** Equipment data checks and maintenance activities accounted for 1 hour and 25 minutes of site usage time. These activities included changing out batteries and routine data checks to ensure the data was being properly recorded/collected. G-TEK spent an additional 3 hours and 20 minutes for breaks and lunches.

**3.4.3.2 Equipment failure or repair.** A total of 20 minutes was needed to resolve equipment failures that occurred while surveying the Woods.

**3.4.3.3 Weather.** No weather delays occurred during the survey.

### **3.4.4 Data Collection**

G-TEK spent a total time of 23 hours and 55 minutes in the Woods, 7 hours and 45 minutes of which was spent collecting data.

### **3.4.5 Demobilization**

The G-TEK survey crew went on to conduct a full demonstration of the site. Therefore, demobilization did not occur until 4 June 2004. On that day, it took the crew 3 hours and 30 minutes to break down and pack up their equipment.

### **3.5 PROCESSING TIME**

G-TEK submitted the raw data from the demonstration activities on the last day of the demonstration, as required. The scoring submittal data was also provided within the required 30-day timeframe.

### **3.6 DEMONSTRATOR'S FIELD PERSONNEL**

Ms. Lynn Helms  
Dr. Malcom Cattach  
Dr. John Stanley  
Mr. Jared Townsend  
Mr. Stephen Griffin

### **3.7 DEMONSTRATOR'S FIELD SURVEYING METHOD**

G-TEK surveyed the woods by surrounding it with the 30 meter by 30 meter cable. Due to the size and shape of the woods, it took G-TEK several setups. They started at the north side of the woods and surveyed in a east/west direction.

### **3.8 SUMMARY OF DAILY LOGS**

Daily logs capture all field activities during this demonstration and are located in Appendix D. Activities pertinent to this specific demonstration are indicated in highlighted text.

## **SECTION 4. TECHNICAL PERFORMANCE RESULTS**

### **4.1 ROC CURVES USING ALL ORDNANCE CATEGORIES**

Figure 2, 4, and 6 shows the probability of detection for the response stage ( $P_d^{\text{res}}$ ) and the discrimination stage ( $P_d^{\text{disc}}$ ) versus their respective probability of false positive for the EM sensor(s), MAG sensor(s) and combined EM/MAG picks respectively. Figure 3, 5, and 7 shows both probabilities plotted against their respective background alarm rate. Both figures use horizontal lines to illustrate the performance of the demonstrator at two demonstrator-specified points: at the system noise level for the response stage, representing the point below which targets are not considered detectable, and at the demonstrator's recommended threshold level for the discrimination stage, defining the subset of targets the demonstrator would recommend digging based on discrimination. Note that all points have been rounded to protect the ground truth.

The overall ground truth is composed of ferrous and non-ferrous anomalies. Due to limitations of the magnetometer, the non-ferrous items cannot be detected. Therefore, the ROC curves presented in figures 4 and 5 of this section are based on the subset of the ground truth that is solely made up of ferrous anomalies.

G-TEK only provided results for the combined EM/MAG for this specific demonstration.

**(Not provided by demonstrator)**

Figure 2. EM Sensor wooded probability of detection for response and discrimination stages versus their respective probability of false positive over all ordnance categories combined.

**(Not provided by demonstrator)**

Figure 3. EM Sensor wooded probability of detection for response and discrimination stages versus their respective background alarm rate over all ordnance categories combined.

**(Not provided by demonstrator)**

Figure 4. MAG Sensor wooded probability of detection for response and discrimination stages versus their respective probability of false positive over all ordnance categories combined.

**(Not provided by demonstrator)**

Figure 5. MAG Sensor wooded probability of detection for response and discrimination stages versus their respective background alarm rate over all ordnance categories combined.




Figure 6. Combined Sensor wood probability of detection for response and discrimination stages versus their respective probability of false positive over all ordnance categories combined.




Figure 7. Combined Sensor wood probability of detection for response and discrimination stages versus their respective background alarm rate over all ordnance categories combined.

## 4.2 ROC CURVES USING ORDNANCE LARGER THAN 20 MM

Figure 8, 10, and 12 shows the probability of detection for the response stage ( $P_d^{\text{res}}$ ) and the discrimination stage ( $P_d^{\text{disc}}$ ) versus their respective probability of false positive when only targets larger than 20 mm are scored for the EM sensor(s), MAG sensor(s) and Combined EM/MAG picks respectively. Figure 9, 11, and 13 shows both probabilities plotted against their respective background alarm rate. Both figures use horizontal lines to illustrate the performance of the demonstrator at two demonstrator-specified points: at the system noise level for the response stage, representing the point below which targets are not considered detectable, and at the demonstrator's recommended threshold level for the discrimination stage, defining the subset of targets the demonstrator would recommend digging based on discrimination. Note that all points have been rounded to protect the ground truth.

The overall ground truth is composed of ferrous and non-ferrous anomalies. Due to limitations of the magnetometer, the non-ferrous items cannot be detected. Therefore, the ROC curves presented in figures 10 and 11 of this section are based on the subset of the ground truth that is solely made up of ferrous anomalies.

G-TEK only provided results for the combined EM/MAG for this specific demonstration.

**(Not provided by demonstrator)**

Figure 8. EM Sensor wood probability of detection for response and discrimination stages versus their respective probability of false positive for all ordnance larger than 20 mm.

**(Not provided by demonstrator)**

Figure 9. EM Sensor wood probability of detection for response and discrimination stages versus their respective background alarm rate for all ordnance larger than 20 mm.

**(Not provided by demonstrator)**

Figure 10. MAG Sensor wood probability of detection for response and discrimination stages versus their respective probability of false positive for all ordnance larger than 20 mm.

**(Not provided by demonstrator)**

Figure 11. MAG Sensor wood probability of detection for response and discrimination stages versus their respective background alarm rate for all ordnance larger than 20 mm.




Figure 12. Combined Sensor wooded probability of detection for response and discrimination stages versus their respective probability of false positive for all ordnance larger than 20 mm.




Figure 13. Combined Sensor wooded probability of detection for response and discrimination stages versus their respective background alarm rate for all ordnance larger than 20 mm.

### 4.3 PERFORMANCE SUMMARIES

Results for the Wooded test broken out by sensor type, size, depth and nonstandard ordnance are presented in Tables 5a, b, and c (for cost results, see section 5). Results by size and depth include both standard and nonstandard ordnance. The results by size show how well the demonstrator did at detecting/discriminating ordnance of a certain caliber range (see app A for size definitions). The results are relative to the number of ordnance items emplaced. Depth is measured from the geometric center of anomalies.

The RESPONSE STAGE results are derived from the list of anomalies above the demonstrator-provided noise level. The results for the DISCRIMINATION STAGE are derived from the demonstrator's recommended threshold for optimizing UXO field cleanup by minimizing false digs and maximizing ordnance recovery. The lower 90-percent confidence limit on probability of detection and  $P_{fp}$  was calculated assuming that the number of detections and false positives are binomially distributed random variables. All results in Table 5 have been rounded to protect the ground truth. However, lower confidence limits were calculated using actual results.

The overall ground truth is composed of ferrous and non-ferrous anomalies. Due to limitations of the magnetometer, the non-ferrous items cannot be detected. Therefore, the summary presented in Table 5b is split exhibiting results based on the subset of the ground truth that is solely the ferrous anomalies and the full ground truth for comparison purposes.

All other tables presented in this section are based on scoring against the ferrous only ground truth. The response stage noise level and recommended discrimination stage threshold values are provided by the demonstrator.

**TABLE 5a. SUMMARY OF WOODED RESULTS FOR THE SAM/SLING (EM SENSOR)**

| Metric                      | Overall | Standard | Nonstandard | By Size |        |       | By Depth, m |           |      |
|-----------------------------|---------|----------|-------------|---------|--------|-------|-------------|-----------|------|
|                             |         |          |             | Small   | Medium | Large | < 0.3       | 0.3 to <1 | >= 1 |
| <b>RESPONSE STAGE</b>       |         |          |             |         |        |       |             |           |      |
| $P_d$                       | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| $P_d$ Low 90% Conf          | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| $P_d$ Upper 90% Conf        | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| $P_{fp}$                    | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| $P_{fp}$ Low 90% Conf       | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| $P_{fp}$ Upper 90% Conf     | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| BAR                         | NA      | -        | -           | -       | -      | -     | -           | -         | -    |
| <b>DISCRIMINATION STAGE</b> |         |          |             |         |        |       |             |           |      |
| $P_d$                       | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| $P_d$ Low 90% Conf          | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| $P_d$ Upper 90% Conf        | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| $P_{fp}$                    | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| $P_{fp}$ Low 90% Conf       | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| $P_{fp}$ Upper 90% Conf     | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| BAR                         | NA      | -        | -           | -       | -      | -     | -           | -         | -    |

Note: G-TEK only provided results for the combined EM/MAG for this specific demonstration.

**TABLE 5b. SUMMARY OF WOODED RESULTS FOR THE SAM/SLING (MAG SENSOR)**

| Metric                         | Overall | Standard | Nonstandard | By Size |        |       | By Depth, m |           |      |
|--------------------------------|---------|----------|-------------|---------|--------|-------|-------------|-----------|------|
|                                |         |          |             | Small   | Medium | Large | < 0.3       | 0.3 to <1 | >= 1 |
| <b>RESPONSE STAGE</b>          |         |          |             |         |        |       |             |           |      |
| P <sub>d</sub>                 | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| P <sub>d</sub> Low 90% Conf    | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| P <sub>d</sub> Upper 90% Conf  | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| P <sub>fp</sub>                | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| P <sub>fp</sub> Low 90% Conf   | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| P <sub>fp</sub> Upper 90% Conf | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| BAR                            | NA      | -        | -           | -       | -      | -     | -           | -         | -    |
| <b>DISCRIMINATION STAGE</b>    |         |          |             |         |        |       |             |           |      |
| P <sub>d</sub>                 | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| P <sub>d</sub> Low 90% Conf    | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| P <sub>d</sub> Upper 90% Conf  | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| P <sub>fp</sub>                | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| P <sub>fp</sub> Low 90% Conf   | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| P <sub>fp</sub> Upper 90% Conf | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| BAR                            | NA      | -        | -           | -       | -      | -     | -           | -         | -    |
| <b>FULL GROUND TRUTH</b>       |         |          |             |         |        |       |             |           |      |
| Metric                         | Overall | Standard | Nonstandard | By Size |        |       | By Depth, m |           |      |
|                                |         |          |             | Small   | Medium | Large | < 0.3       | 0.3 to <1 | >= 1 |
| <b>RESPONSE STAGE</b>          |         |          |             |         |        |       |             |           |      |
| P <sub>d</sub>                 | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| P <sub>d</sub> Low 90% Conf    | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| P <sub>d</sub> Upper 90% Conf  | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| P <sub>fp</sub>                | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| P <sub>fp</sub> Low 90% Conf   | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| P <sub>fp</sub> Upper 90% Conf | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| BAR                            | NA      | -        | -           | -       | -      | -     | -           | -         | -    |
| <b>DISCRIMINATION STAGE</b>    |         |          |             |         |        |       |             |           |      |
| P <sub>d</sub>                 | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| P <sub>d</sub> Low 90% Conf    | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| P <sub>d</sub> Upper 90% Conf  | NA      | NA       | NA          | NA      | NA     | NA    | NA          | NA        | NA   |
| P <sub>fp</sub>                | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| P <sub>fp</sub> Low 90% Conf   | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| P <sub>fp</sub> Upper 90% Conf | NA      | -        | -           | -       | -      | -     | NA          | NA        | NA   |
| BAR                            | NA      | -        | -           | -       | -      | -     | -           | -         | -    |

Response Stage Noise Level: NA

Recommended Discrimination Stage Threshold: NA

Note: G-TEK only provided results for the combined EM/MAG for this specific demonstration.

**TABLE 5c. SUMMARY OF WOODED RESULTS FOR THE SAM/SLING**

| Metric                         | Overall | Standard | Nonstandard | By Size |        |       | By Depth, m |           |      |
|--------------------------------|---------|----------|-------------|---------|--------|-------|-------------|-----------|------|
|                                |         |          |             | Small   | Medium | Large | < 0.3       | 0.3 to <1 | >= 1 |
| <b>RESPONSE STAGE</b>          |         |          |             |         |        |       |             |           |      |
| P <sub>d</sub>                 | 0.10    | 0.10     | 0.10        | 0.00    | 0.20   | 0.30  | 0.10        | 0.10      | 0.05 |
| P <sub>d</sub> Low 90% Conf    | 0.08    | 0.08     | 0.04        | 0.00    | 0.12   | 0.17  | 0.07        | 0.07      | 0.01 |
| P <sub>d</sub> Upper 90% Conf  | 0.15    | 0.18     | 0.16        | 0.04    | 0.28   | 0.47  | 0.17        | 0.19      | 0.21 |
| P <sub>fp</sub>                | 0.35    | -        | -           | -       | -      | -     | 0.30        | 0.40      | 0.30 |
| P <sub>fp</sub> Low 90% Conf   | 0.31    | -        | -           | -       | -      | -     | 0.26        | 0.34      | 0.19 |
| P <sub>fp</sub> Upper 90% Conf | 0.37    | -        | -           | -       | -      | -     | 0.35        | 0.42      | 0.42 |
| BAR                            | 0.15    | -        | -           | -       | -      | -     | -           | -         | -    |
| <b>DISCRIMINATION STAGE</b>    |         |          |             |         |        |       |             |           |      |
| P <sub>d</sub>                 | 0.05    | 0.10     | 0.05        | 0.00    | 0.10   | 0.15  | 0.10        | 0.05      | 0.00 |
| P <sub>d</sub> Low 90% Conf    | 0.04    | 0.05     | 0.01        | 0.00    | 0.06   | 0.06  | 0.05        | 0.03      | 0.00 |
| P <sub>d</sub> Upper 90% Conf  | 0.10    | 0.13     | 0.09        | 0.04    | 0.19   | 0.30  | 0.13        | 0.13      | 0.13 |
| P <sub>fp</sub>                | 0.10    | -        | -           | -       | -      | -     | 0.10        | 0.10      | 0.05 |
| P <sub>fp</sub> Low 90% Conf   | 0.08    | -        | -           | -       | -      | -     | 0.07        | 0.08      | 0.02 |
| P <sub>fp</sub> Upper 90% Conf | 0.12    | -        | -           | -       | -      | -     | 0.13        | 0.14      | 0.15 |
| BAR                            | 0.05    | -        | -           | -       | -      | -     | -           | -         | -    |

Response Stage Noise Level: -4.84

Recommended Discrimination Stage Threshold: 0.99

Note: The recommended discrimination stage threshold values are provided by the demonstrator.

#### 4.4 EFFICIENCY, REJECTION RATES, AND TYPE CLASSIFICATION (All results based on combined EM/MAG data set)

Efficiency and rejection rates are calculated to quantify the discrimination ability at specific points of interest on the ROC curve: (1) at the point where no decrease in P<sub>d</sub> is suffered (i.e., the efficiency is by definition equal to one) and (2) at the operator selected threshold. These values are reported in Table 6.

**TABLE 6. EFFICIENCY AND REJECTION RATES**

|                                | Efficiency (E) | False Positive Rejection Rate | Background Alarm Rejection Rate |
|--------------------------------|----------------|-------------------------------|---------------------------------|
| At Operating Point             | 0.61           | 0.70                          | 0.49                            |
| With No Loss of P <sub>d</sub> | 1.00           | 0.11                          | 0.06                            |

At the demonstrator's recommended setting, the ordnance items that were detected and correctly discriminated were further scored on whether their correct type could be identified (table 7). Correct type examples include "20-mm projectile, 105-mm HEAT Projectile, and 2.75-inch Rocket". A list of the standard type declaration required for each ordnance item was provided to demonstrators prior to testing. For example, the standard type for the three example items are 20mmP, 105H, and 2.75in, respectively.

**TABLE 7. CORRECT TYPE CLASSIFICATION  
OF TARGETS CORRECTLY  
DISCRIMINATED AS UXO**

| Size    | Percentage Correct |
|---------|--------------------|
| Small   | 0.00               |
| Medium  | 0.00               |
| Large   | 0.00               |
| Overall | 0.00               |

Note: The demonstrator did not attempt to provide type classification.

#### **4.5 LOCATION ACCURACY**

The mean location error and standard deviations appear in Table 8. These calculations are based on average missed depth for ordnance correctly identified in the discrimination stage. Depths are measured from the closest point of the ordnance to the surface. For the Blind Grid, only depth errors are calculated, since (X, Y) positions are known to be the centers of each grid square.

**TABLE 8. MEAN LOCATION ERROR AND  
STANDARD DEVIATION (M)**

|          | Mean  | Standard Deviation |
|----------|-------|--------------------|
| Northing | -0.15 | 0.17               |
| Easting  | 0.07  | 0.30               |
| Depth    | 0.10  | 0.27               |

## **SECTION 5. ON-SITE LABOR COSTS**

A standardized estimate for labor costs associated with this effort was calculated as follows: the first person at the test site was designated “supervisor”, the second person was designated “data analyst”, and the third and following personnel were considered “field support”. Standardized hourly labor rates were charged by title: supervisor at \$95.00/hour, data analyst at \$57.00/hour, and field support at \$28.50/hour.

Government representatives monitored on-site activity. All on-site activities were grouped into one of ten categories: initial setup/mobilization, daily setup/stop, calibration, collecting data, downtime due to break/lunch, downtime due to equipment failure, downtime due to equipment/data checks or maintenance, downtime due to weather, downtime due to demonstration site issue, or demobilization. See Appendix D for the daily activity log. See section 3.4 for a summary of field activities.

The standardized cost estimate associated with the labor needed to perform the field activities is presented in Table 9. Note that calibration time includes time spent in the Calibration Lanes as well as field calibrations. “Site survey time” includes daily setup/stop time, collecting data, breaks/lunch, downtime due to equipment/data checks or maintenance, downtime due to failure, and downtime due to weather.

**TABLE 9. ON-SITE LABOR COSTS**

|                      | No. People | Hourly Wage | Hours | Cost              |
|----------------------|------------|-------------|-------|-------------------|
| <b>Initial Setup</b> |            |             |       |                   |
| Supervisor           | 1          | \$95.00     | 5.0   | \$475.00          |
| Data Analyst         | 1          | 57.00       | 5.0   | 285.00            |
| Field Support        | 3          | 28.50       | 5.0   | 427.50            |
| SubTotal             |            |             |       | <b>\$1,187.50</b> |
| <b>Calibration</b>   |            |             |       |                   |
| Supervisor           | 1          | \$95.00     | 2.66  | \$252.70          |
| Data Analyst         | 1          | 57.00       | 2.66  | 151.62            |
| Field Support        | 3          | 28.50       | 2.66  | 227.43            |
| SubTotal             |            |             |       | <b>\$631.75</b>   |
| <b>Site Survey</b>   |            |             |       |                   |
| Supervisor           | 1          | \$95.00     | 23.92 | \$2,272.40        |
| Data Analyst         | 1          | 57.00       | 23.92 | 1,363.44          |
| Field Support        | 2          | 28.50       | 23.92 | 1,363.44          |
| SubTotal             |            |             |       | <b>\$4,999.28</b> |

See notes at end of table.

**TABLE 9 (CONT'D)**

|                       | <b>No. People</b> | <b>Hourly Wage</b> | <b>Hours</b> | <b>Cost</b>       |
|-----------------------|-------------------|--------------------|--------------|-------------------|
| <b>Demobilization</b> |                   |                    |              |                   |
| Supervisor            | 1                 | \$95.00            | 3.50         | \$332.50          |
| Data Analyst          | 1                 | 57.00              | 3.50         | 199.50            |
| Field Support         | 2                 | 28.50              | 3.50         | 199.50            |
| Subtotal              |                   |                    |              | <b>\$731.50</b>   |
| Total                 |                   |                    |              | <b>\$7,550.03</b> |

Notes: Calibration time includes time spent in the Calibration Lanes as well as calibration before each data run.

Site Survey time includes daily setup/stop time, collecting data, breaks/lunch, downtime due to system maintenance, failure, and weather.

## **SECTION 6. COMPARISON OF RESULTS TO OPEN FIELD DEMONSTRATION (BASED ON COMBINED EM/MAG DATA SETS)**

### **6.1 SUMMARY OF RESULTS FROM OPEN FIELD DEMONSTRATION**

Table 10 shows the results from the Open Field survey conducted prior to surveying the Wooded during the same site visit in June of 2004. Due to the system utilizing magnetometer type sensors, all results presented in the following section have been based on performance scoring against the ferrous only ground truth anomalies. For more details on the Blind Grid survey results reference section 2.1.6.

**TABLE 10. SUMMARY OF OPEN FIELD RESULTS FOR THE SAM/SLING**

| Metric                         | Overall | Standard | Nonstandard | By Size |        |       | By Depth, m |           |      |
|--------------------------------|---------|----------|-------------|---------|--------|-------|-------------|-----------|------|
|                                |         |          |             | Small   | Medium | Large | < 0.3       | 0.3 to <1 | >= 1 |
| <b>RESPONSE STAGE</b>          |         |          |             |         |        |       |             |           |      |
| P <sub>d</sub>                 | 0.45    | 0.45     | 0.35        | 0.20    | 0.50   | 0.75  | 0.40        | 0.45      | 0.45 |
| P <sub>d</sub> Low 90% Conf    | 0.39    | 0.42     | 0.31        | 0.17    | 0.45   | 0.65  | 0.36        | 0.37      | 0.36 |
| P <sub>d</sub> Upper 90% Conf  | 0.46    | 0.52     | 0.42        | 0.26    | 0.57   | 0.79  | 0.47        | 0.49      | 0.53 |
| P <sub>fp</sub>                | 0.40    | -        | -           | -       | -      | -     | 0.35        | 0.45      | 0.65 |
| P <sub>fp</sub> Low 90% Conf   | 0.36    | -        | -           | -       | -      | -     | 0.30        | 0.40      | 0.43 |
| P <sub>fp</sub> Upper 90% Conf | 0.40    | -        | -           | -       | -      | -     | 0.35        | 0.46      | 0.79 |
| BAR                            | 0.05    | -        | -           | -       | -      | -     | -           | -         | -    |
| <b>DISCRIMINATION STAGE</b>    |         |          |             |         |        |       |             |           |      |
| P <sub>d</sub>                 | 0.30    | 0.30     | 0.25        | 0.20    | 0.40   | 0.25  | 0.35        | 0.20      | 0.30 |
| P <sub>d</sub> Low 90% Conf    | 0.26    | 0.28     | 0.19        | 0.17    | 0.33   | 0.21  | 0.28        | 0.17      | 0.23 |
| P <sub>d</sub> Upper 90% Conf  | 0.32    | 0.37     | 0.29        | 0.26    | 0.45   | 0.35  | 0.38        | 0.28      | 0.39 |
| P <sub>fp</sub>                | 0.15    | -        | -           | -       | -      | -     | 0.15        | 0.20      | 0.20 |
| P <sub>fp</sub> Low 90% Conf   | 0.16    | -        | -           | -       | -      | -     | 0.13        | 0.17      | 0.07 |
| P <sub>fp</sub> Upper 90% Conf | 0.19    | -        | -           | -       | -      | -     | 0.17        | 0.22      | 0.37 |
| BAR                            | 0.05    | -        | -           | -       | -      | -     | -           | -         | -    |

### **6.2 COMPARISON OF ROC CURVES USING ALL ORDNANCE CATEGORIES**

Figure 6 shows P<sub>d</sub><sup>res</sup> versus the respective P<sub>fp</sub> over all ordnance categories. Figure 7 shows P<sub>d</sub><sup>disc</sup> versus their respective P<sub>fp</sub> over all ordnance categories. Figure 7 uses horizontal lines to illustrate the performance of the demonstrator at the recommended discrimination threshold levels, defining the subset of targets the demonstrator would recommend digging based on discrimination. The ROC curves in this section are a sole reflection of the ferrous only survey.




Figure 6. SAM/Sling dual mode  $P_d^{\text{res}}$  stages versus the respective  $P_{fp}$  over all ordnance categories combined.




Figure 7. SAM/Sling dual mode  $P_d^{\text{disc}}$  versus the respective  $P_{fp}$  over all ordnance categories combined.

### 6.3 COMPARISON OF ROC CURVES USING ORDNANCE LARGER THAN 20 MM

Figure 8 shows the  $P_d^{\text{res}}$  versus the respective probability of  $P_{fp}$  over ordnance larger than 20 mm. Figure 9 shows  $P_d^{\text{disc}}$  versus the respective  $P_{fp}$  over ordnance larger than 20 mm. Figure 9 uses horizontal lines to illustrate the performance of the demonstrator at the recommended discrimination threshold levels, defining the subset of targets the demonstrator would recommend digging based on discrimination.




Figure 8. SAM/Sling dual mode  $P_d^{\text{res}}$  versus the respective  $P_{fp}$  for ordnance larger than 20 mm.




Figure 9. SAM/Sling dual mode  $P_d^{\text{disc}}$  versus the respective  $P_{fp}$  for ordnance larger than 20 mm.

#### 6.4 STATISTICAL COMPARISONS

Statistical Chi-square significance tests were used to compare results between the Woods and Open Field scenarios. The intent of the comparison is to determine if the feature introduced in each scenario has a degrading effect on the performance of the sensor system. However, any modifications in the UXO sensor system during the test, like changes in the processing or changes in the selection of the operating threshold, will also contribute to performance differences.

The Chi-square test for comparison between ratios was used at a significance level of 0.05 to compare Woods to Open Field with regard to  $P_d^{\text{res}}$ ,  $P_d^{\text{disc}}$ ,  $P_{fp}^{\text{res}}$  and  $P_{fp}^{\text{disc}}$ , Efficiency and Rejection Rate. These results are presented in Table 11. A detailed explanation and example of the Chi-square application is located in Appendix A.

**TABLE 11. CHI-SQUARE RESULTS – WOODS VERSUS OPEN FIELD**

| Metric                 | Small           | Medium          | Large           | Overall         |
|------------------------|-----------------|-----------------|-----------------|-----------------|
| $P_d^{\text{res}}$     | Significant     | Significant     | Significant     | Significant     |
| $P_d^{\text{disc}}$    | Significant     | Significant     | Not Significant | Significant     |
| $P_{fp}^{\text{res}}$  | Not Significant | Not Significant | Not Significant | Not Significant |
| $P_{fp}^{\text{disc}}$ | -               | -               | -               | Not Significant |
| Efficiency             | -               |                 |                 | Significant     |
| Rejection rate         | -               | -               | -               | Significant     |

## **SECTION 7. APPENDIXES**

### **APPENDIX A. TERMS AND DEFINITIONS**

#### **GENERAL DEFINITIONS**

Anomaly: Location of a system response deemed to warrant further investigation by the demonstrator for consideration as an emplaced ordnance item.

Detection: An anomaly location that is within  $R_{\text{halo}}$  of an emplaced ordnance item.

Emplaced Ordnance: An ordnance item buried by the government at a specified location in the test site.

Emplaced Clutter: A clutter item (i.e., non-ordnance item) buried by the government at a specified location in the test site.

$R_{\text{halo}}$ : A pre-determined radius about the periphery of an emplaced item (clutter or ordnance) within which a location identified by the demonstrator as being of interest is considered to be a response from that item. If multiple declarations lie within  $R_{\text{halo}}$  of any item (clutter or ordnance), the declaration with the highest signal output within the  $R_{\text{halo}}$  will be utilized. For the purpose of this program, a circular halo 0.5 meters in radius will be placed around the center of the object for all clutter and ordnance items less than 0.6 meters in length. When ordnance items are longer than 0.6 meters, the halo becomes an ellipse where the minor axis remains 1 meter and the major axis is equal to the length of the ordnance plus 1 meter.

Small Ordnance: Caliber of ordnance less than or equal to 40 mm (includes 20-mm projectile, 40-mm projectile, submunitions BLU-26, BLU-63, and M42).

Medium Ordnance: Caliber of ordnance greater than 40 mm and less than or equal to 81 mm (includes 57-mm projectile, 60-mm mortar, 2.75 in. Rocket, MK118 Rockeye, 81-mm mortar).

Large Ordnance: Caliber of ordnance greater than 81 mm (includes 105-mm HEAT, 105-mm projectile, 155-mm projectile, 500-pound bomb).

Shallow: Items buried less than 0.3 meter below ground surface.

Medium: Items buried greater than or equal to 0.3 meter and less than 1 meter below ground surface.

Deep: Items buried greater than or equal to 1 meter below ground surface.

Response Stage Noise Level: The level that represents the point below which anomalies are not considered detectable. Demonstrators are required to provide the recommended noise level for the Blind Grid test area.

**Discrimination Stage Threshold:** The demonstrator selected threshold level that they believe provides optimum performance of the system by retaining all detectable ordnance and rejecting the maximum amount of clutter. This level defines the subset of anomalies the demonstrator would recommend digging based on discrimination.

**Binomially Distributed Random Variable:** A random variable of the type which has only two possible outcomes, say success and failure, is repeated for  $n$  independent trials with the probability  $p$  of success and the probability  $1-p$  of failure being the same for each trial. The number of successes  $x$  observed in the  $n$  trials is an estimate of  $p$  and is considered to be a binomially distributed random variable.

## RESPONSE AND DISCRIMINATION STAGE DATA

The scoring of the demonstrator's performance is conducted in two stages. These two stages are termed the RESPONSE STAGE and DISCRIMINATION STAGE. For both stages, the probability of detection ( $P_d$ ) and the false alarms are reported as receiver operating characteristic (ROC) curves. False alarms are divided into those anomalies that correspond to emplaced clutter items, measuring the probability of false positive ( $P_{fp}$ ) and those that do not correspond to any known item, termed background alarms.

The RESPONSE STAGE scoring evaluates the ability of the system to detect emplaced targets without regard to ability to discriminate ordnance from other anomalies. For the RESPONSE STAGE, the demonstrator provides the scoring committee with the location and signal strength of all anomalies that the demonstrator has deemed sufficient to warrant further investigation and/or processing as potential emplaced ordnance items. This list is generated with minimal processing (e.g., this list will include all signals above the system noise threshold). As such, it represents the most inclusive list of anomalies.

The DISCRIMINATION STAGE evaluates the demonstrator's ability to correctly identify ordnance as such, and to reject clutter. For the same locations as in the RESPONSE STAGE anomaly list, the DISCRIMINATION STAGE list contains the output of the algorithms applied in the discrimination-stage processing. This list is prioritized based on the demonstrator's determination that an anomaly location is likely to contain ordnance. Thus, higher output values are indicative of higher confidence that an ordnance item is present at the specified location. For electronic signal processing, priority ranking is based on algorithm output. For other systems, priority ranking is based on human judgment. The demonstrator also selects the threshold that the demonstrator believes will provide "optimum" system performance, (i.e., that retains all the detected ordnance and rejects the maximum amount of clutter).

Note: The two lists provided by the demonstrator contain identical numbers of potential target locations. They differ only in the priority ranking of the declarations.

## RESPONSE STAGE DEFINITIONS

Response Stage Probability of Detection ( $P_d^{\text{res}}$ ):  $P_d^{\text{res}} = (\text{No. of response-stage detections}) / (\text{No. of emplaced ordnance in the test site})$ .

Response Stage False Positive ( $fp^{\text{res}}$ ): An anomaly location that is within  $R_{\text{halo}}$  of an emplaced clutter item.

Response Stage Probability of False Positive ( $P_{fp}^{\text{res}}$ ):  $P_{fp}^{\text{res}} = (\text{No. of response-stage false positives}) / (\text{No. of emplaced clutter items})$ .

Response Stage Background Alarm ( $ba^{\text{res}}$ ): An anomaly in a blind grid cell that contains neither emplaced ordnance nor an emplaced clutter item. An anomaly location in the open field or scenarios that is outside  $R_{\text{halo}}$  of any emplaced ordnance or emplaced clutter item.

Response Stage Probability of Background Alarm ( $P_{ba}^{\text{res}}$ ): Blind Grid only:  $P_{ba}^{\text{res}} = (\text{No. of response-stage background alarms}) / (\text{No. of empty grid locations})$ .

Response Stage Background Alarm Rate (BAR $^{\text{res}}$ ): Open Field only:  $\text{BAR}^{\text{res}} = (\text{No. of response-stage background alarms}) / (\text{arbitrary constant})$ .

Note that the quantities  $P_d^{\text{res}}$ ,  $P_{fp}^{\text{res}}$ ,  $P_{ba}^{\text{res}}$ , and  $\text{BAR}^{\text{res}}$  are functions of  $t^{\text{res}}$ , the threshold applied to the response-stage signal strength. These quantities can therefore be written as  $P_d^{\text{res}}(t^{\text{res}})$ ,  $P_{fp}^{\text{res}}(t^{\text{res}})$ ,  $P_{ba}^{\text{res}}(t^{\text{res}})$ , and  $\text{BAR}^{\text{res}}(t^{\text{res}})$ .

## DISCRIMINATION STAGE DEFINITIONS

Discrimination: The application of a signal processing algorithm or human judgment to response-stage data that discriminates ordnance from clutter. Discrimination should identify anomalies that the demonstrator has high confidence correspond to ordnance, as well as those that the demonstrator has high confidence correspond to nonordnance or background returns. The former should be ranked with highest priority and the latter with lowest.

Discrimination Stage Probability of Detection ( $P_d^{\text{disc}}$ ):  $P_d^{\text{disc}} = (\text{No. of discrimination-stage detections}) / (\text{No. of emplaced ordnance in the test site})$ .

Discrimination Stage False Positive ( $fp^{\text{disc}}$ ): An anomaly location that is within  $R_{\text{halo}}$  of an emplaced clutter item.

Discrimination Stage Probability of False Positive ( $P_{fp}^{\text{disc}}$ ):  $P_{fp}^{\text{disc}} = (\text{No. of discrimination stage false positives}) / (\text{No. of emplaced clutter items})$ .

Discrimination Stage Background Alarm ( $ba^{\text{disc}}$ ): An anomaly in a blind grid cell that contains neither emplaced ordnance nor an emplaced clutter item. An anomaly location in the open field or scenarios that is outside  $R_{\text{halo}}$  of any emplaced ordnance or emplaced clutter item.

Discrimination Stage Probability of Background Alarm ( $P_{ba}^{disc}$ ):  $P_{ba}^{disc} = (\text{No. of discrimination-stage background alarms}) / (\text{No. of empty grid locations})$ .

Discrimination Stage Background Alarm Rate (BAR<sup>disc</sup>): BAR<sup>disc</sup> = (No. of discrimination-stage background alarms)/(arbitrary constant).

Note that the quantities  $P_d^{\text{disc}}$ ,  $P_{fp}^{\text{disc}}$ ,  $P_{ba}^{\text{disc}}$ , and  $\text{BAR}^{\text{disc}}$  are functions of  $t^{\text{disc}}$ , the threshold applied to the discrimination-stage signal strength. These quantities can therefore be written as  $P_d^{\text{disc}}(t^{\text{disc}})$ ,  $P_{fp}^{\text{disc}}(t^{\text{disc}})$ ,  $P_{ba}^{\text{disc}}(t^{\text{disc}})$ , and  $\text{BAR}^{\text{disc}}(t^{\text{disc}})$ .

## RECEIVER-OPERATING CHARACTERISTIC (ROC) CURVES

ROC curves at both the response and discrimination stages can be constructed based on the above definitions. The ROC curves plot the relationship between  $P_d$  versus  $P_{fp}$  and  $P_d$  versus BAR or  $P_{ba}$  as the threshold applied to the signal strength is varied from its minimum ( $t_{min}$ ) to its maximum ( $t_{max}$ ) value.<sup>1</sup> Figure A-1 shows how  $P_d$  versus  $P_{fp}$  and  $P_d$  versus BAR are combined into ROC curves. Note that the “res” and “disc” superscripts have been suppressed from all the variables for clarity.




Figure A-1. ROC curves for open field testing. Each curve applies to both the response and discrimination stages.

<sup>1</sup>Strictly speaking, ROC curves plot the  $P_d$  versus  $P_{fa}$  over a pre-determined and fixed number of detection opportunities (some of the opportunities are located over ordnance and others are located over clutter or blank spots). In an open field scenario, each system suppresses its signal strength reports until some bare-minimum signal response is received by the system.

Consequently, the open field ROC curves do not have information from low signal-output locations, and, furthermore, different contractors report their signals over a different set of locations on the ground. These ROC curves are thus not true to the strict definition of ROC curves as defined in textbooks on detection theory. Note, however, that the ROC curves obtained in the Blind Grid test sites are true ROC curves.

## METRICS TO CHARACTERIZE THE DISCRIMINATION STAGE

The demonstrator is also scored on efficiency and rejection ratio, which measure the effectiveness of the discrimination stage processing. The goal of discrimination is to retain the greatest number of ordnance detections from the anomaly list, while rejecting the maximum number of anomalies arising from nonordnance items. The efficiency measures the amount of detected ordnance retained by the discrimination, while the rejection ratio measures the fraction of false alarms rejected. Both measures are defined relative to the entire response list, i.e., the maximum ordnance detectable by the sensor and its accompanying false positive rate or background alarm rate.

Efficiency (E):  $E = P_d^{\text{disc}}(t^{\text{disc}})/P_d^{\text{res}}(t_{\min}^{\text{res}})$ ; Measures (at a threshold of interest), the degree to which the maximum theoretical detection performance of the sensor system (as determined by the response stage  $t_{\min}$ ) is preserved after application of discrimination techniques. Efficiency is a number between 0 and 1. An efficiency of 1 implies that all of the ordnance initially detected in the response stage was retained at the specified threshold in the discrimination stage,  $t^{\text{disc}}$ .

False Positive Rejection Rate ( $R_{fp}$ ):  $R_{fp} = 1 - [P_{fp}^{\text{disc}}(t^{\text{disc}})/P_{fp}^{\text{res}}(t_{\min}^{\text{res}})]$ ; Measures (at a threshold of interest), the degree to which the sensor system's false positive performance is improved over the maximum false positive performance (as determined by the response stage  $t_{\min}$ ). The rejection rate is a number between 0 and 1. A rejection rate of 1 implies that all emplaced clutter initially detected in the response stage were correctly rejected at the specified threshold in the discrimination stage.

Background Alarm Rejection Rate ( $R_{ba}$ ):

Blind Grid:  $R_{ba} = 1 - [P_{ba}^{\text{disc}}(t^{\text{disc}})/P_{ba}^{\text{res}}(t_{\min}^{\text{res}})]$ .

Open Field:  $R_{ba} = 1 - [\text{BAR}^{\text{disc}}(t^{\text{disc}})/\text{BAR}^{\text{res}}(t_{\min}^{\text{res}})]$ .

Measures the degree to which the discrimination stage correctly rejects background alarms initially detected in the response stage. The rejection rate is a number between 0 and 1. A rejection rate of 1 implies that all background alarms initially detected in the response stage were rejected at the specified threshold in the discrimination stage.

## CHI-SQUARE COMPARISON EXPLANATION:

The Chi-square test for differences in probabilities (or 2 x 2 contingency table) is used to analyze two samples drawn from two different populations to see if both populations have the same or different proportions of elements in a certain category. More specifically, two random samples are drawn, one from each population, to test the null hypothesis that the probability of event A (some specified event) is the same for both populations (ref 3).

A 2 x 2 contingency table is used in the Standardized UXO Technology Demonstration Site Program to determine if there is reason to believe that the proportion of ordnance correctly detected/discriminated by demonstrator X's system is significantly degraded by the more challenging terrain feature introduced. The test statistic of the 2 x 2 contingency table is the

Chi-square distribution with one degree of freedom. Since an association between the more challenging terrain feature and relatively degraded performance is sought, a one-sided test is performed. A significance level of 0.05 is chosen which sets a critical decision limit of 2.71 from the Chi-square distribution with one degree of freedom. It is a critical decision limit because if the test statistic calculated from the data exceeds this value, the two proportions tested will be considered significantly different. If the test statistic calculated from the data is less than this value, the two proportions tested will be considered not significantly different.

An exception must be applied when either a 0 or 100 percent success rate occurs in the sample data. The Chi-square test cannot be used in these instances. Instead, Fischer's test is used and the critical decision limit for one-sided tests is the chosen significance level, which in this case is 0.05. With Fischer's test, if the test statistic is less than the critical value, the proportions are considered to be significantly different.

Standardized UXO Technology Demonstration Site examples, where blind grid results are compared to those from the open field and open field results are compared to those from one of the scenarios, follow. It should be noted that a significant result does not prove a cause and effect relationship exists between the two populations of interest; however, it does serve as a tool to indicate that one data set has experienced a degradation in system performance at a large enough level than can be accounted for merely by chance or random variation. Note also that a result that is not significant indicates that there is not enough evidence to declare that anything more than chance or random variation within the same population is at work between the two data sets being compared.

Demonstrator X achieves the following overall results after surveying each of the three progressively more difficult areas using the same system (results indicate the number of ordnance detected divided by the number of ordnance emplaced):

|                     | Blind Grid    | Open Field | Moguls      |
|---------------------|---------------|------------|-------------|
| $P_d^{\text{res}}$  | 100/100 = 1.0 | 8/10 = .80 | 20/33 = .61 |
| $P_d^{\text{disc}}$ | 80/100 = 0.80 | 6/10 = .60 | 8/33 = .24  |

$P_d^{\text{res}}$ : BLIND GRID versus OPEN FIELD. Using the example data above to compare probabilities of detection in the response stage, all 100 ordnance out of 100 emplaced ordnance items were detected in the blind grid while 8 ordnance out of 10 emplaced were detected in the open field. Fischer's test must be used since a 100 percent success rate occurs in the data. Fischer's test uses the four input values to calculate a test statistic of 0.0075 that is compared against the critical value of 0.05. Since the test statistic is less than the critical value, the smaller response stage detection rate (0.80) is considered to be significantly less at the 0.05 level of significance. While a significant result does not prove a cause and effect relationship exists between the change in survey area and degradation in performance, it does indicate that the detection ability of demonstrator X's system seems to have been degraded in the open field relative to results from the blind grid using the same system.

$P_d^{\text{disc}}$ : BLIND GRID versus OPEN FIELD. Using the example data above to compare probabilities of detection in the discrimination stage, 80 out of 100 emplaced ordnance items were correctly discriminated as ordnance in blind grid testing while 6 ordnance out of 10 emplaced were correctly discriminated as such in open field-testing. Those four values are used to calculate a test statistic of 1.12. Since the test statistic is less than the critical value of 2.71, the two discrimination stage detection rates are considered to be not significantly different at the 0.05 level of significance.

$P_d^{\text{res}}$ : OPEN FIELD versus MOGULS. Using the example data above to compare probabilities of detection in the response stage, 8 out of 10 and 20 out of 33 are used to calculate a test statistic of 0.56. Since the test statistic is less than the critical value of 2.71, the two response stage detection rates are considered to be not significantly different at the 0.05 level of significance.

$P_d^{\text{disc}}$ : OPEN FIELD versus MOGULS. Using the example data above to compare probabilities of detection in the discrimination stage, 6 out of 10 and 8 out of 33 are used to calculate a test statistic of 2.98. Since the test statistic is greater than the critical value of 2.71, the smaller discrimination stage detection rate is considered to be significantly less at the 0.05 level of significance. While a significant result does not prove a cause and effect relationship exists between the change in survey area and degradation in performance, it does indicate that the ability of demonstrator X to correctly discriminate seems to have been degraded by the mogul terrain relative to results from the flat open field using the same system.

## APPENDIX B. DAILY WEATHER LOGS

TABLE B-1. WEATHER LOG

| Date      | Time | Average Temperature, °F | Total Precipitation, in. |
|-----------|------|-------------------------|--------------------------|
| 5/24/2004 | 0700 | 76.3                    | 0.00                     |
| 5/24/2004 | 0800 | 78.6                    | 0.00                     |
| 5/24/2004 | 0900 | 80.3                    | 0.00                     |
| 5/24/2004 | 1000 | 82.3                    | 0.00                     |
| 5/24/2004 | 1100 | 83.9                    | 0.00                     |
| 5/24/2004 | 1200 | 85.7                    | 0.00                     |
| 5/24/2004 | 1300 | 86.4                    | 0.00                     |
| 5/24/2004 | 1400 | 87.5                    | 0.00                     |
| 5/24/2004 | 1500 | 87.4                    | 0.00                     |
| 5/24/2004 | 1600 | 86.5                    | 0.00                     |
| 5/24/2004 | 1700 | 86.3                    | 0.00                     |
| 5/25/2004 | 0700 | 72.5                    | 0.00                     |
| 5/25/2004 | 0800 | 74.5                    | 0.00                     |
| 5/25/2004 | 0900 | 76.9                    | 0.00                     |
| 5/25/2004 | 1000 | 78.8                    | 0.00                     |
| 5/25/2004 | 1100 | 81.4                    | 0.00                     |
| 5/25/2004 | 1200 | 83.2                    | 0.00                     |
| 5/25/2004 | 1300 | 84.8                    | 0.00                     |
| 5/25/2004 | 1400 | 84.0                    | 0.00                     |
| 5/25/2004 | 1500 | 85.3                    | 0.00                     |
| 5/25/2004 | 1600 | 85.4                    | 0.00                     |
| 5/25/2004 | 1700 | 85.2                    | 0.00                     |
| 5/26/2004 | 0700 | 68.9                    | 0.00                     |
| 5/26/2004 | 0800 | 70.4                    | 0.00                     |
| 5/26/2004 | 0900 | 73.3                    | 0.00                     |
| 5/26/2004 | 1000 | 73.6                    | 0.00                     |
| 5/26/2004 | 1100 | 74.6                    | 0.00                     |
| 5/26/2004 | 1200 | 75.3                    | 0.00                     |
| 5/26/2004 | 1300 | 84.4                    | 0.00                     |
| 5/26/2004 | 1400 | 76.3                    | 0.00                     |
| 5/26/2004 | 1500 | 77.1                    | 0.00                     |
| 5/26/2004 | 1600 | 77.4                    | 0.00                     |
| 5/26/2004 | 1700 | 77.8                    | 0.00                     |
| 5/27/2004 | 0700 | 67.1                    | 0.00                     |
| 5/27/2004 | 0800 | 69.7                    | 0.00                     |
| 5/27/2004 | 0900 | 71.7                    | 0.00                     |
| 5/27/2004 | 1000 | 73.6                    | 0.00                     |
| 5/27/2004 | 1100 | 76.2                    | 0.00                     |
| 5/27/2004 | 1200 | 77.1                    | 0.00                     |
| 5/27/2004 | 1300 | 77.5                    | 0.00                     |
| 5/27/2004 | 1400 | 79.1                    | 0.00                     |
| 5/27/2004 | 1500 | 80.4                    | 0.00                     |
| 5/27/2004 | 1600 | 80.6                    | 0.00                     |
| 5/27/2004 | 1700 | 79.4                    | 0.00                     |

**TABLE B-1. (CONT'D)**

| Date      | Time | Average Temperature, °F | Total Precipitation, in. |
|-----------|------|-------------------------|--------------------------|
| 5/28/2004 | 0700 | 71.2                    | 0.00                     |
| 5/28/2004 | 0800 | 72.2                    | 0.00                     |
| 5/28/2004 | 0900 | 74.3                    | 0.00                     |
| 5/28/2004 | 1000 | 75.0                    | 0.00                     |
| 5/28/2004 | 1100 | 77.1                    | 0.00                     |
| 5/28/2004 | 1200 | 78.3                    | 0.00                     |
| 5/28/2004 | 1300 | 79.0                    | 0.00                     |
| 5/28/2004 | 1400 | 78.9                    | 0.00                     |
| 5/28/2004 | 1500 | 79.7                    | 0.00                     |
| 5/28/2004 | 1600 | 78.0                    | 0.00                     |
| 5/28/2004 | 1700 | 79.1                    | 0.00                     |
| 5/29/2004 | 0700 | 59.5                    | 0.00                     |
| 5/29/2004 | 0800 | 60.5                    | 0.00                     |
| 5/29/2004 | 0900 | 61.6                    | 0.00                     |
| 5/29/2004 | 1000 | 63.3                    | 0.00                     |
| 5/29/2004 | 1100 | 65.0                    | 0.00                     |
| 5/29/2004 | 1200 | 66.9                    | 0.00                     |
| 5/29/2004 | 1300 | 68.6                    | 0.00                     |
| 5/29/2004 | 1400 | 69.8                    | 0.00                     |
| 5/29/2004 | 1500 | 70.8                    | 0.00                     |
| 5/29/2004 | 1600 | 70.9                    | 0.00                     |
| 5/29/2004 | 1700 | 70.8                    | 0.00                     |
| 5/30/2004 | 0700 | 61.1                    | 0.00                     |
| 5/30/2004 | 0800 | 64.3                    | 0.00                     |
| 5/30/2004 | 0900 | 65.2                    | 0.00                     |
| 5/30/2004 | 1000 | 67.2                    | 0.00                     |
| 5/30/2004 | 1100 | 68.5                    | 0.00                     |
| 5/30/2004 | 1200 | 70.4                    | 0.00                     |
| 5/30/2004 | 1300 | 72.8                    | 0.00                     |
| 5/30/2004 | 1400 | 72.7                    | 0.00                     |
| 5/30/2004 | 1500 | 72.3                    | 0.00                     |
| 5/30/2004 | 1600 | 71.7                    | 0.00                     |
| 5/30/2004 | 1700 | 71.7                    | 0.00                     |
| 5/31/2004 | 0700 | 66.9                    | 0.00                     |
| 5/31/2004 | 0800 | 66.9                    | 0.00                     |
| 5/31/2004 | 0900 | 66.9                    | 0.00                     |
| 5/31/2004 | 1000 | 66.7                    | 0.00                     |
| 5/31/2004 | 1100 | 65.6                    | 0.00                     |
| 5/31/2004 | 1200 | 65.6                    | 0.00                     |
| 5/31/2004 | 1300 | 66.4                    | 0.00                     |
| 5/31/2004 | 1400 | 66.6                    | 0.00                     |
| 5/31/2004 | 1500 | 66.1                    | 0.00                     |
| 5/31/2004 | 1600 | 66.8                    | 0.00                     |
| 5/31/2004 | 1700 | 67.5                    | 0.00                     |

**TABLE B-1. (CONT'D)**

| Date      | Time | Average Temperature, °F | Total Precipitation, in. |
|-----------|------|-------------------------|--------------------------|
| 6/01/2004 | 0700 | 65.5                    | 0.00                     |
| 6/01/2004 | 0800 | 68.0                    | 0.00                     |
| 6/01/2004 | 0900 | 70.3                    | 0.00                     |
| 6/01/2004 | 1000 | 72.9                    | 0.00                     |
| 6/01/2004 | 1100 | 73.1                    | 0.00                     |
| 6/01/2004 | 1200 | 78.2                    | 0.00                     |
| 6/01/2004 | 1300 | 79.4                    | 0.00                     |
| 6/01/2004 | 1400 | 77.5                    | 0.00                     |
| 6/01/2004 | 1500 | 74.5                    | 0.00                     |
| 6/01/2004 | 1600 | 64.2                    | 0.00                     |
| 6/01/2004 | 1700 | 68.5                    | 0.00                     |
| 6/02/2004 | 0700 | 62.3                    | 0.00                     |
| 6/02/2004 | 0800 | 67.1                    | 0.00                     |
| 6/02/2004 | 0900 | 71.9                    | 0.00                     |
| 6/02/2004 | 1000 | 74.0                    | 0.00                     |
| 6/02/2004 | 1100 | 76.3                    | 0.00                     |
| 6/02/2004 | 1200 | 78.5                    | 0.00                     |
| 6/02/2004 | 1300 | 79.4                    | 0.00                     |
| 6/02/2004 | 1400 | 79.5                    | 0.00                     |
| 6/02/2004 | 1500 | 76.0                    | 0.00                     |
| 6/02/2004 | 1600 | 74.0                    | 0.00                     |
| 6/02/2004 | 1700 | 76.5                    | 0.00                     |
| 6/03/2004 | 0700 | 64.3                    | 0.00                     |
| 6/03/2004 | 0800 | 67.8                    | 0.00                     |
| 6/03/2004 | 0900 | 69.9                    | 0.00                     |
| 6/03/2004 | 1000 | 72.4                    | 0.00                     |
| 6/03/2004 | 1100 | 73.0                    | 0.00                     |
| 6/03/2004 | 1200 | 74.5                    | 0.00                     |
| 6/03/2004 | 1300 | 76.1                    | 0.00                     |
| 6/03/2004 | 1400 | 77.4                    | 0.00                     |
| 6/03/2004 | 1500 | 77.9                    | 0.00                     |
| 6/03/2004 | 1600 | 77.9                    | 0.00                     |
| 6/03/2004 | 1700 | 78.4                    | 0.00                     |
| 6/04/2004 | 0700 | 64.6                    | 0.00                     |
| 6/04/2004 | 0800 | 65.9                    | 0.00                     |
| 6/04/2004 | 0900 | 67.4                    | 0.00                     |
| 6/04/2004 | 1000 | 69.0                    | 0.00                     |
| 6/04/2004 | 1100 | 70.9                    | 0.00                     |
| 6/04/2004 | 1200 | 72.5                    | 0.00                     |
| 6/04/2004 | 1300 | 72.6                    | 0.00                     |
| 6/04/2004 | 1400 | 72.2                    | 0.00                     |
| 6/04/2004 | 1500 | 71.1                    | 0.00                     |
| 6/04/2004 | 1600 | 70.4                    | 0.00                     |
| 6/04/2004 | 1700 | 69.3                    | 0.00                     |

## APPENDIX C. SOIL MOISTURE

Date: 24 May 2004

Time: 0715 through 1700 hours

| Probe Location    | Layer, in. | AM Reading, % | PM Reading, % |
|-------------------|------------|---------------|---------------|
| Wet Area          | 0 to 6     | NA            | NA            |
|                   | 6 to 12    |               |               |
|                   | 12 to 24   |               |               |
|                   | 24 to 36   |               |               |
|                   | 36 to 48   |               |               |
| Wooded Area       | 0 to 6     | NA            | NA            |
|                   | 6 to 12    |               |               |
|                   | 12 to 24   |               |               |
|                   | 24 to 36   |               |               |
|                   | 36 to 48   |               |               |
| Open Area         | 0 to 6     | NA            | NA            |
|                   | 6 to 12    |               |               |
|                   | 12 to 24   |               |               |
|                   | 24 to 36   |               |               |
|                   | 36 to 48   |               |               |
| Calibration Lanes | 0 to 6     | 39.2          | 39.0          |
|                   | 6 to 12    | 37.5          | 38.0          |
|                   | 12 to 24   | 1.5           | 1.6           |
|                   | 24 to 36   | 4.2           | 4.1           |
|                   | 36 to 48   | 5.3           | 5.5           |
| Blind Grid/Moguls | 0 to 6     | 3.2           | 3.0           |
|                   | 6 to 12    | 23.5          | 23.6          |
|                   | 12 to 24   | 38.2          | 39.0          |
|                   | 24 to 36   | 36.9          | 37.3          |
|                   | 36 to 48   | 38.2          | 38.1          |

Date: 25 May 2004  
Time: 0715 through 1700 hours

| <b>Probe Location</b> | <b>Layer, in.</b> | <b>AM Reading, %</b> | <b>PM Reading, %</b> |
|-----------------------|-------------------|----------------------|----------------------|
| Wet Area              | 0 to 6            | 60.3                 | 50.6                 |
|                       | 6 to 12           | 74.2                 | 60.1                 |
|                       | 12 to 24          | 76.9                 | 74.5                 |
|                       | 24 to 36          | 54.9                 | 77.3                 |
|                       | 36 to 48          | 50.3                 | 55.3                 |
| Wooded Area           | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |
| Open Area             | 0 to 6            | 21.9                 | 21.6                 |
|                       | 6 to 12           | 6.3                  | 5.8                  |
|                       | 12 to 24          | 18.1                 | 18.0                 |
|                       | 24 to 36          | 26.8                 | 27.3                 |
|                       | 36 to 48          | 51.9                 | 52.6                 |
| Calibration Lanes     | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |
| Blind Grid/Moguls     | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |

Date: 27 May 2004  
 Time: 0715 through 1700 hours

| <b>Probe Location</b> | <b>Layer, in.</b> | <b>AM Reading, %</b> | <b>PM Reading, %</b> |
|-----------------------|-------------------|----------------------|----------------------|
| Wet Area              | 0 to 6            | 60.8                 | 60.4                 |
|                       | 6 to 12           | 75.7                 | 75.9                 |
|                       | 12 to 24          | 77.2                 | 77.0                 |
|                       | 24 to 36          | 56.6                 | 56.2                 |
|                       | 36 to 48          | 49.5                 | 50.0                 |
| Wooded Area           | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |
| Open Area             | 0 to 6            | 21.5                 | 21.2                 |
|                       | 6 to 12           | 5.4                  | 5.8                  |
|                       | 12 to 24          | 18.9                 | 19.3                 |
|                       | 24 to 36          | 27.6                 | 27.9                 |
|                       | 36 to 48          | 52.1                 | 52.4                 |
| Calibration Lanes     | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |
| Blind Grid/Moguls     | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |

Date: 28 May 2004  
 Time: 0715 through 1700 hours

| <b>Probe Location</b> | <b>Layer, in.</b> | <b>AM Reading, %</b> | <b>PM Reading, %</b> |
|-----------------------|-------------------|----------------------|----------------------|
| Wet Area              | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |
| Wooded Area           | 0 to 6            | 15.2                 | 15.0                 |
|                       | 6 to 12           | 5.8                  | 6.0                  |
|                       | 12 to 24          | 4.7                  | 4.5                  |
|                       | 24 to 36          | 52.3                 | 52.4                 |
|                       | 36 to 48          | 54.3                 | 54.9                 |
| Open Area             | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |
| Calibration Lanes     | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |
| Blind Grid/Moguls     | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |

Date: 29 May 2004  
Time: 0715 through 1700 hours

| <b>Probe Location</b> | <b>Layer, in.</b> | <b>AM Reading, %</b> | <b>PM Reading, %</b> |
|-----------------------|-------------------|----------------------|----------------------|
| Wet Area              | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |
| Wooded Area           | 0 to 6            | 15.4                 | 15.3                 |
|                       | 6 to 12           | 6.3                  | 6.4                  |
|                       | 12 to 24          | 4.8                  | 4.8                  |
|                       | 24 to 36          | 52.9                 | 53.2                 |
|                       | 36 to 48          | 55.4                 | 55.7                 |
| Open Area             | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |
| Calibration Lanes     | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |
| Blind Grid/Moguls     | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |

Date: 1 June 2004

Time: 0715 through 1700 hours

| Probe Location    | Layer, in. | AM Reading, % | PM Reading, % |
|-------------------|------------|---------------|---------------|
| Wet Area          | 0 to 6     | 60.4          | 60.2          |
|                   | 6 to 12    | 75.9          | 76.2          |
|                   | 12 to 24   | 77.0          | 77.3          |
|                   | 24 to 36   | 56.2          | 56.1          |
|                   | 36 to 48   | 50.0          | 50.6          |
| Wooded Area       | 0 to 6     | 15.3          | 15.2          |
|                   | 6 to 12    | 6.4           | 6.5           |
|                   | 12 to 24   | 4.8           | 5.3           |
|                   | 24 to 36   | 53.2          | 53.6          |
|                   | 36 to 48   | 55.7          | 56.1          |
| Open Area         | 0 to 6     | 21.2          | 21.0          |
|                   | 6 to 12    | 5.8           | 5.9           |
|                   | 12 to 24   | 19.3          | 19.7          |
|                   | 24 to 36   | 27.9          | 28.3          |
|                   | 36 to 48   | 52.4          | 52.7          |
| Calibration Lanes | 0 to 6     | NA            | NA            |
|                   | 6 to 12    |               |               |
|                   | 12 to 24   |               |               |
|                   | 24 to 36   |               |               |
|                   | 36 to 48   |               |               |
| Blind Grid/Moguls | 0 to 6     | NA            | NA            |
|                   | 6 to 12    |               |               |
|                   | 12 to 24   |               |               |
|                   | 24 to 36   |               |               |
|                   | 36 to 48   |               |               |

Date: 2 June 2004

Time: 0715 through 1700 hours

| <b>Probe Location</b> | <b>Layer, in.</b> | <b>AM Reading, %</b> | <b>PM Reading, %</b> |
|-----------------------|-------------------|----------------------|----------------------|
| Wet Area              | 0 to 6            | 59.4                 | 59.2                 |
|                       | 6 to 12           | 76.8                 | 77.1                 |
|                       | 12 to 24          | 77.1                 | 77.4                 |
|                       | 24 to 36          | 56.8                 | 57.2                 |
|                       | 36 to 48          | 50.4                 | 50.8                 |
| Wooded Area           | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |
| Open Area             | 0 to 6            | 21.0                 | 21.1                 |
|                       | 6 to 12           | 5.9                  | 6.2                  |
|                       | 12 to 24          | 19.7                 | 20.1                 |
|                       | 24 to 36          | 28.3                 | 28.4                 |
|                       | 36 to 48          | 52.7                 | 53.0                 |
| Calibration Lanes     | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |
| Blind Grid/Moguls     | 0 to 6            | NA                   | NA                   |
|                       | 6 to 12           |                      |                      |
|                       | 12 to 24          |                      |                      |
|                       | 24 to 36          |                      |                      |
|                       | 36 to 48          |                      |                      |

Date: 3 June 2004

Time: 0715 through 1700 hours

| Probe Location    | Layer, in. | AM Reading, % | PM Reading, % |
|-------------------|------------|---------------|---------------|
| Wet Area          | 0 to 6     | 59.4          | 59.2          |
|                   | 6 to 12    | 77.4          | 77.2          |
|                   | 12 to 24   | 77.3          | 77.1          |
|                   | 24 to 36   | 57.5          | 57.2          |
|                   | 36 to 48   | 51.7          | 52.0          |
| Wooded Area       | 0 to 6     | NA            | NA            |
|                   | 6 to 12    |               |               |
|                   | 12 to 24   |               |               |
|                   | 24 to 36   |               |               |
|                   | 36 to 48   |               |               |
| Open Area         | 0 to 6     | 21.1          | 21.3          |
|                   | 6 to 12    | 6.2           | 6.4           |
|                   | 12 to 24   | 20.1          | 20.3          |
|                   | 24 to 36   | 28.4          | 28.9          |
|                   | 36 to 48   | 53.0          | 53.1          |
| Calibration Lanes | 0 to 6     | NA            | NA            |
|                   | 6 to 12    |               |               |
|                   | 12 to 24   |               |               |
|                   | 24 to 36   |               |               |
|                   | 36 to 48   |               |               |
| Blind Grid/Moguls | 0 to 6     | 3.6           | 3.2           |
|                   | 6 to 12    | 23.5          | 23.8          |
|                   | 12 to 24   | 36.7          | 37.1          |
|                   | 24 to 36   | 35.4          | 35.2          |
|                   | 36 to 48   | 38.1          | 38.3          |

Date: 4 June 2004

Time: 0715 through 1700 hours

| Probe Location    | Layer, in. | AM Reading, % | PM Reading, % |
|-------------------|------------|---------------|---------------|
| Wet Area          | 0 to 6     | NA            | NA            |
|                   | 6 to 12    |               |               |
|                   | 12 to 24   |               |               |
|                   | 24 to 36   |               |               |
|                   | 36 to 48   |               |               |
| Wooded Area       | 0 to 6     | NA            | NA            |
|                   | 6 to 12    |               |               |
|                   | 12 to 24   |               |               |
|                   | 24 to 36   |               |               |
|                   | 36 to 48   |               |               |
| Open Area         | 0 to 6     | NA            | NA            |
|                   | 6 to 12    |               |               |
|                   | 12 to 24   |               |               |
|                   | 24 to 36   |               |               |
|                   | 36 to 48   |               |               |
| Calibration Lanes | 0 to 6     | NA            | NA            |
|                   | 6 to 12    |               |               |
|                   | 12 to 24   |               |               |
|                   | 24 to 36   |               |               |
|                   | 36 to 48   |               |               |
| Blind Grid/Moguls | 0 to 6     | 3.5           | 3.2           |
|                   | 6 to 12    | 24.3          | 23.8          |
|                   | 12 to 24   | 37.5          | 37.4          |
|                   | 24 to 36   | 35.7          | 35.4          |
|                   | 36 to 48   | 38.4          | 38.8          |

**APPENDIX D. DAILY ACTIVITY LOGS**

D-1

| Date      | No. of People | Area Tested      | Status Start Time | Status Stop Time | Duration, min | Operational Status         | OP Stat Code | Operational Status - Comments | Track Method | Track Method=Other Explain | Pattern | Field Conditions |
|-----------|---------------|------------------|-------------------|------------------|---------------|----------------------------|--------------|-------------------------------|--------------|----------------------------|---------|------------------|
| 5/24/2004 | 5             | CALIBRATION LANE | 800               | 1215             | 255           | INITIAL MOBILIZATION       | 1            | INITIAL MOBILIZATION          | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/24/2004 | 5             | CALIBRATION LANE | 1215              | 1245             | 30            | LUNCH/BREAK                | 5            | LUNCH/BREAK                   | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/24/2004 | 5             | CALIBRATION LANE | 1245              | 1330             | 45            | INITIAL MOBILIZATION       | 1            | INITIAL MOBILIZATION          | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/24/2004 | 5             | CALIBRATION LANE | 1330              | 1445             | 75            | COLLECT DATA               | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/24/2004 | 5             | BLIND TEST GRID  | 1445              | 1500             | 15            | DAILY START/STOP           | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/24/2004 | 5             | BLIND TEST GRID  | 1500              | 1530             | 30            | COLLECT DATA               | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/24/2004 | 5             | BLIND TEST GRID  | 1530              | 1555             | 25            | DOWNTIME MAINTENANCE CHECK | 7            | CHANGE BATTERY                | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/24/2004 | 5             | BLIND TEST GRID  | 1555              | 1630             | 35            | COLLECT DATA               | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/24/2004 | 5             | CALIBRATION LANE | 1630              | 1640             | 10            | DAILY START/STOP           | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/24/2004 | 5             | CALIBRATION LANE | 1640              | 1705             | 25            | COLLECT DATA               | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/24/2004 | 5             | CALIBRATION LANE | 1705              | 1725             | 20            | DAILY START/STOP           | 3            | END OF DAILY OPERATIONS       | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD       | 755               | 855              | 60            | DAILY START/STOP           | 3            | START OF DAILY OPERATIONS     | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD       | 855               | 915              | 20            | COLLECT DATA               | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD       | 915               | 920              | 5             | DAILY START/STOP           | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |

Note: Activities pertinent to this specific demonstration are indicated in highlighted text.

| Date      | No. of People | Area Tested | Status Start Time | Status Stop Time | Duration, min | Operational Status | OP Stat Code | Operational Status - Comments | Track Method | Track Method=Other Explain | Pattern | Field Conditions |
|-----------|---------------|-------------|-------------------|------------------|---------------|--------------------|--------------|-------------------------------|--------------|----------------------------|---------|------------------|
| 5/25/2004 | 5             | OPEN FIELD  | 920               | 940              | 20            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 940               | 945              | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 945               | 1005             | 20            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1005              | 1015             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1015              | 1040             | 25            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1040              | 1050             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1050              | 1110             | 20            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1110              | 1120             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1120              | 1140             | 20            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1140              | 1150             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1150              | 1215             | 25            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1215              | 1315             | 60            | LUNCH/BREAK        | 5            | LUNCH/BREAK                   | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1315              | 1340             | 25            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1340              | 1350             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1350              | 1405             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |

| Date      | No. of People | Area Tested | Status Start Time | Status Stop Time | Duration, min | Operational Status         | OP Stat Code | Operational Status - Comments           | Track Method | Track Method=Other Explain | Pattern | Field Conditions |
|-----------|---------------|-------------|-------------------|------------------|---------------|----------------------------|--------------|---|--------------|----------------------------|---------|------------------|
| 5/25/2004 | 5             | OPEN FIELD  | 1405              | 1415             | 10            | DAILY START/STOP           | 3            | SET UP, MOVE CABLES                     | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1415              | 1430             | 15            | COLLECT DATA               | 4            | COLLECT DATA                            | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1430              | 1445             | 15            | DOWNTIME MAINTENANCE CHECK | 7            | CHANGE BATTERY                          | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1445              | 1455             | 10            | DAILY START/STOP           | 3            | SET UP, MOVE CABLES                     | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1455              | 1515             | 20            | COLLECT DATA               | 4            | COLLECT DATA                            | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1515              | 1520             | 5             | DAILY START/STOP           | 3            | SET UP, MOVE CABLES                     | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1520              | 1535             | 15            | COLLECT DATA               | 4            | COLLECT DATA                            | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1535              | 1540             | 5             | DAILY START/STOP           | 3            | SET UP, MOVE CABLES                     | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1540              | 1600             | 20            | COLLECT DATA               | 4            | COLLECT DATA                            | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/25/2004 | 5             | OPEN FIELD  | 1600              | 1615             | 15            | DAILY START/STOP           | 3            | END OF DAILY OPERATIONS                 | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/26/2004 | 5             | OPEN FIELD  | 750               | 1150             | 240           | DAILY START/STOP           | 3            | START OF DAILY OPERATIONS, SET UP GRIDS | GPS          | NA                         | LINEAR  | CLOUDY RAIN      |
| 5/26/2004 | 5             | OPEN FIELD  | 1150              | 1250             | 60            | LUNCH/BREAK                | 5            | LUNCH/BREAK                             | GPS          | NA                         | LINEAR  | CLOUDY RAIN      |
| 5/26/2004 | 5             | OPEN FIELD  | 1250              | 1310             | 20            | DAILY START/STOP           | 3            | SET UP, MOVE CABLES                     | GPS          | NA                         | LINEAR  | CLOUDY RAIN      |
| 5/26/2004 | 5             | OPEN FIELD  | 1310              | 1330             | 20            | COLLECT DATA               | 4            | COLLECT DATA                            | GPS          | NA                         | LINEAR  | CLOUDY RAIN      |

| Date      | No. of People | Area Tested | Status Start Time | Status Stop Time | Duration, min | Operational Status | OP Stat Code | Operational Status - Comments | Track Method | Track Method=Other Explain | Pattern | Field Conditions |
|-----------|---------------|-------------|-------------------|------------------|---------------|--------------------|--------------|-------------------------------|--------------|----------------------------|---------|------------------|
| 5/26/2004 | 5             | OPEN FIELD  | 1330              | 1500             | 90            | LUNCH/BREAK        | 5            | LUNCH/BREAK                   | GPS          | NA                         | LINEAR  | CLOUDY RAIN      |
| 5/26/2004 | 5             | OPEN FIELD  | 1500              | 1515             | 15            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY RAIN      |
| 5/26/2004 | 5             | OPEN FIELD  | 1515              | 1540             | 25            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY RAIN      |
| 5/26/2004 | 5             | OPEN FIELD  | 1540              | 1545             | 15            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY RAIN      |
| 5/26/2004 | 5             | OPEN FIELD  | 1545              | 1605             | 20            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY RAIN      |
| 5/26/2004 | 5             | OPEN FIELD  | 1605              | 1610             | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY RAIN      |
| 5/26/2004 | 5             | OPEN FIELD  | 1610              | 1625             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY RAIN      |
| 5/26/2004 | 5             | OPEN FIELD  | 1625              | 1630             | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY RAIN      |
| 5/26/2004 | 5             | OPEN FIELD  | 1630              | 1645             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY RAIN      |
| 5/26/2004 | 5             | OPEN FIELD  | 1645              | 1705             | 20            | DAILY START/STOP   | 3            | END OF DAILY OPERATIONS       | GPS          | NA                         | LINEAR  | CLOUDY RAIN      |
| 5/27/2004 | 5             | OPEN FIELD  | 755               | 815              | 20            | DAILY START/STOP   | 3            | START OF DAILY OPERATIONS     | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 815               | 830              | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 830               | 835              | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 835               | 845              | 10            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |

| Date      | No. of People | Area Tested | Status Start Time | Status Stop Time | Duration, min | Operational Status | OP Stat Code | Operational Status - Comments | Track Method | Track Method=Other Explain | Pattern | Field Conditions |
|-----------|---------------|-------------|-------------------|------------------|---------------|--------------------|--------------|-------------------------------|--------------|----------------------------|---------|------------------|
| 5/27/2004 | 5             | OPEN FIELD  | 845               | 850              | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 850               | 905              | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 905               | 910              | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 910               | 925              | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 925               | 930              | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 930               | 945              | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 945               | 950              | 5             | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 950               | 1005             | 15            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1005              | 1010             | 5             | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1010              | 1025             | 15            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1025              | 1105             | 40            | LUNCH/BREAK        | 5            | LUNCH/BREAK                   | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1105              | 1110             | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1110              | 1125             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1125              | 1130             | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1130              | 1145             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |

| Date      | No. of People | Area Tested | Status Start Time | Status Stop Time | Duration, min | Operational Status         | OP Stat Code | Operational Status - Comments | Track Method | Track Method=Other Explain | Pattern | Field Conditions |
|-----------|---------------|-------------|-------------------|------------------|---------------|----------------------------|--------------|-------------------------------|--------------|----------------------------|---------|------------------|
| 5/27/2004 | 5             | OPEN FIELD  | 1145              | 1150             | 5             | DAILY START/STOP           | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1150              | 1155             | 5             | DOWNTIME MAINTENANCE CHECK | 7            | CHANGE BATTERY                | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1155              | 1210             | 15            | COLLECT DATA               | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1210              | 1215             | 5             | DAILY START/STOP           | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1215              | 1230             | 15            | COLLECT DATA               | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1230              | 1340             | 70            | LUNCH/BREAK                | 5            | LUNCH/BREAK                   | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1340              | 1400             | 20            | COLLECT DATA               | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1400              | 1410             | 10            | DAILY START/STOP           | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1410              | 1420             | 10            | COLLECT DATA               | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1420              | 1425             | 5             | DAILY START/STOP           | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1425              | 1440             | 15            | COLLECT DATA               | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1440              | 1445             | 5             | DAILY START/STOP           | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1445              | 1505             | 20            | COLLECT DATA               | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1505              | 1515             | 10            | DAILY START/STOP           | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1515              | 1530             | 15            | COLLECT DATA               | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |

| Date      | No. of People | Area Tested | Status Start Time | Status Stop Time | Duration, min | Operational Status | OP Stat Code | Operational Status - Comments | Track Method | Track Method=Other Explain | Pattern | Field Conditions |
|-----------|---------------|-------------|-------------------|------------------|---------------|--------------------|--------------|-------------------------------|--------------|----------------------------|---------|------------------|
| 5/27/2004 | 5             | OPEN FIELD  | 1530              | 1535             | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1535              | 1555             | 20            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1555              | 1600             | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1600              | 1615             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/27/2004 | 5             | OPEN FIELD  | 1615              | 1700             | 45            | DAILY START/STOP   | 3            | END OF DAILY OPERATIONS       | GPS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/28/2004 | 4             | WOODS       | 800               | 1115             | 195           | DAILY START/STOP   | 3            | SET UP RTS SYSTEM             | RTS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/28/2004 | 4             | WOODS       | 1115              | 1145             | 30            | COLLECT DATA       | 4            | COLLECT DATA                  | RTS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/28/2004 | 4             | WOODS       | 1145              | 1150             | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | RTS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/28/2004 | 4             | WOODS       | 1150              | 1255             | 65            | LUNCH/BREAK        | 5            | LUNCH/BREAK                   | RTS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/28/2004 | 4             | WOODS       | 1255              | 1310             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | RTS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/28/2004 | 4             | WOODS       | 1310              | 1315             | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | RTS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/28/2004 | 4             | WOODS       | 1315              | 1340             | 25            | COLLECT DATA       | 4            | COLLECT DATA                  | RTS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/28/2004 | 4             | WOODS       | 1340              | 1350             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | RTS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/28/2004 | 4             | WOODS       | 1350              | 1530             | 100           | DAILY START/STOP   | 3            | SET UP, MOVE RTS              | RTS          | NA                         | LINEAR  | CLOUDY MUDDY     |

Note: Activities pertinent to this specific demonstration are indicated in highlighted text.

| Date      | No. of People | Area Tested | Status Start Time | Status Stop Time | Duration, min | Operational Status         | OP Stat Code | Operational Status - Comments    | Track Method | Track Method=Other Explain | Pattern | Field Conditions |
|-----------|---------------|-------------|-------------------|------------------|---------------|----------------------------|--------------|----------------------------------|--------------|----------------------------|---------|------------------|
| 5/28/2004 | 4             | WOODS       | 1530              | 1600             | 30            | COLLECT DATA               | 4            | COLLECT DATA                     | RTS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/28/2004 | 4             | WOODS       | 1600              | 1630             | 30            | DAILY START/STOP           | 3            | END OF DAILY OPERATIONS          | RTS          | NA                         | LINEAR  | CLOUDY MUDDY     |
| 5/29/2004 | 4             | WOODS       | 805               | 835              | 35            | DAILY START/STOP           | 3            | START OF DAILY OPERATIONS        | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/29/2004 | 4             | WOODS       | 835               | 900              | 25            | COLLECT DATA               | 4            | COLLECT DATA                     | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/29/2004 | 4             | WOODS       | 900               | 1145             | 165           | DAILY START/STOP           | 3            | SET UP, CABLES, MOVE RTS         | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/29/2004 | 4             | WOODS       | 1145              | 1315             | 90            | COLLECT DATA               | 4            | COLLECT DATA                     | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/29/2004 | 4             | WOODS       | 1315              | 1415             | 60            | LUNCH/BREAK                | 5            | LUNCH/BREAK                      | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/29/2004 | 4             | WOODS       | 1415              | 1445             | 30            | DOWNTIME MAINTENANCE CHECK | 7            | DATA CHECK                       | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/29/2004 | 4             | WOODS       | 1445              | 1500             | 15            | COLLECT DATA               | 4            | COLLECT DATA                     | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/29/2004 | 4             | WOODS       | 1500              | 1520             | 20            | DAILY START/STOP           | 3            | SET UP, MOVE CABLES              | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/29/2004 | 4             | WOODS       | 1520              | 1600             | 40            | COLLECT DATA               | 4            | COLLECT DATA                     | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/29/2004 | 4             | WOODS       | 1600              | 1620             | 20            | EQUIPMENT FAILURE          | 6            | DEAD RTS BATTERY, NO REPLACEMENT | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 5/29/2004 | 4             | WOODS       | 1620              | 1640             | 20            | DAILY START/STOP           | 3            | END OF DAILY OPERATIONS          | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |

Note: Activities pertinent to this specific demonstration are indicated in highlighted text.

| Date     | No. of People | Area Tested | Status Start Time | Status Stop Time | Duration, min | Operational Status         | OP Stat Code | Operational Status - Comments | Track Method | Track Method=Other Explain | Pattern | Field Conditions |
|----------|---------------|-------------|-------------------|------------------|---------------|----------------------------|--------------|-------------------------------|--------------|----------------------------|---------|------------------|
| 6/1/2004 | 4             | WOODS       | 810               | 845              | 35            | DAILY START/STOP           | 3            | START OF DAILY OPERATIONS     | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/1/2004 | 4             | WOODS       | 845               | 1035             | 110           | COLLECT DATA               | 4            | COLLECT DATA                  | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/1/2004 | 4             | WOODS       | 1035              | 1100             | 25            | DOWNTIME MAINTENANCE CHECK | 7            | DATA CHECK                    | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/1/2004 | 4             | WOODS       | 1100              | 1120             | 20            | COLLECT DATA               | 4            | COLLECT DATA                  | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/1/2004 | 4             | WOODS       | 1120              | 1205             | 45            | DAILY START/STOP           | 3            | SET UP, MOVE RTS              | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/1/2004 | 4             | WOODS       | 1205              | 1310             | 65            | COLLECT DATA               | 4            | COLLECT DATA                  | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/1/2004 | 4             | WOODS       | 1310              | 1425             | 75            | LUNCH/BREAK                | 5            | LUNCH/BREAK                   | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/1/2004 | 4             | WOODS       | 1425              | 1455             | 30            | DOWNTIME MAINTENANCE CHECK | 7            | DATA CHECK                    | RTS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/1/2004 | 4             | OPEN FIELD  | 1455              | 1530             | 35            | DAILY START/STOP           | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/1/2004 | 4             | OPEN FIELD  | 1530              | 1545             | 15            | COLLECT DATA               | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/1/2004 | 4             | OPEN FIELD  | 1545              | 1605             | 20            | DAILY START/STOP           | 3            | END OF DAILY OPERATIONS       | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 755               | 855              | 60            | DAILY START/STOP           | 3            | START OF DAILY OPERATIONS     | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 855               | 910              | 15            | COLLECT DATA               | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 910               | 915              | 5             | DAILY START/STOP           | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |

Note: Activities pertinent to this specific demonstration are indicated in highlighted text.

| Date     | No. of People | Area Tested | Status Start Time | Status Stop Time | Duration, min | Operational Status | OP Stat Code | Operational Status - Comments | Track Method | Track Method=Other Explain | Pattern | Field Conditions |       |
|----------|---------------|-------------|-------------------|------------------|---------------|--------------------|--------------|-------------------------------|--------------|----------------------------|---------|------------------|-------|
| 6/2/2004 | 4             | OPEN FIELD  | 915               | 1025             | 70            | LUNCH/BREAK        | 5            | LUNCH/BREAK                   | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/2/2004 | 4             | OPEN FIELD  | 1025              | 1035             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/2/2004 | 4             | OPEN FIELD  | 1035              | 1050             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/2/2004 | 4             | OPEN FIELD  | 1050              | 1105             | 15            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/2/2004 | 4             | OPEN FIELD  | 1105              | 1115             | 10            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/2/2004 | 4             | OPEN FIELD  | 1115              | 1135             | 20            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/2/2004 | 4             | OPEN FIELD  | 1135              | 1145             | 10            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/2/2004 | 4             | OPEN FIELD  | 1145              | 1205             | 20            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/2/2004 | 4             | OPEN FIELD  | 1205              | 1215             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/2/2004 | 4             | OPEN FIELD  | 1215              | 1225             | 10            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/2/2004 | 4             | OPEN FIELD  | 1225              | 1230             | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/2/2004 | 4             | OPEN FIELD  | 1230              | 1245             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/2/2004 | 4             | OPEN FIELD  | 1245              | 1340             | 55            | LUNCH/BREAK        | 5            | LUNCH/BREAK                   | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/2/2004 | 4             | OPEN FIELD  | 1340              | 1350             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |

| Date     | No. of People | Area Tested | Status Start Time | Status Stop Time | Duration, min | Operational Status | OP Stat Code | Operational Status - Comments | Track Method | Track Method=Other Explain | Pattern | Field Conditions |
|----------|---------------|-------------|-------------------|------------------|---------------|--------------------|--------------|-------------------------------|--------------|----------------------------|---------|------------------|
| 6/2/2004 | 4             | OPEN FIELD  | 1350              | 1405             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 1405              | 1410             | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 1410              | 1420             | 10            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 1420              | 1430             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 1430              | 1440             | 10            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 1440              | 1450             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 1450              | 1510             | 20            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 1510              | 1520             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 1520              | 1525             | 5             | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 1525              | 1535             | 10            | WEATHER            | 8            | RAIN                          | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 1535              | 1540             | 5             | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 1540              | 1550             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 1550              | 1600             | 10            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 1600              | 1610             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/2/2004 | 4             | OPEN FIELD  | 1610              | 1625             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |

| Date     | No. of People | Area Tested | Status Start Time | Status Stop Time | Duration, min | Operational Status | OP Stat Code | Operational Status - Comments | Track Method | Track Method=Other Explain | Pattern | Field Conditions |       |
|----------|---------------|-------------|-------------------|------------------|---------------|--------------------|--------------|-------------------------------|--------------|----------------------------|---------|------------------|-------|
| 6/2/2004 | 4             | OPEN FIELD  | 1625              | 1640             | 15            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/2/2004 | 4             | OPEN FIELD  | 1640              | 1655             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/2/2004 | 4             | OPEN FIELD  | 1655              | 1715             | 20            | DAILY START/STOP   | 3            | END OF DAILY OPERATIONS       | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/3/2004 | 4             | OPEN FIELD  | 805               | 840              | 25            | DAILY START/STOP   | 3            | START OF DAILY OPERATIONS     | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/3/2004 | 4             | OPEN FIELD  | 840               | 850              | 10            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/3/2004 | 4             | OPEN FIELD  | 850               | 855              | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/3/2004 | 4             | OPEN FIELD  | 855               | 910              | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/3/2004 | 4             | OPEN FIELD  | 910               | 915              | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/3/2004 | 4             | OPEN FIELD  | 915               | 920              | 5             | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/3/2004 | 4             | OPEN FIELD  | 920               | 945              | 25            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/3/2004 | 4             | OPEN FIELD  | 945               | 1005             | 20            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/3/2004 | 4             | OPEN FIELD  | 1005              | 1025             | 20            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/3/2004 | 4             | OPEN FIELD  | 1025              | 1040             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/3/2004 | 4             | OPEN FIELD  | 1040              | 1045             | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/3/2004 | 4             | OPEN FIELD  | 1045              | 1100             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |

| Date     | No. of People | Area Tested | Status Start Time | Status Stop Time | Duration, min | Operational Status | OP Stat Code | Operational Status - Comments | Track Method | Track Method=Other Explain | Pattern | Field Conditions |
|----------|---------------|-------------|-------------------|------------------|---------------|--------------------|--------------|-------------------------------|--------------|----------------------------|---------|------------------|
| 6/3/2004 | 4             | MOGUL AREA  | 1100              | 1110             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/3/2004 | 4             | MOGUL AREA  | 1110              | 1130             | 20            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/3/2004 | 4             | MOGUL AREA  | 1130              | 1150             | 20            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/3/2004 | 4             | MOGUL AREA  | 1150              | 1305             | 75            | LUNCH/BREAK        | 5            | LUNCH/BREAK                   | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/3/2004 | 4             | MOGUL AREA  | 1305              | 1325             | 20            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/3/2004 | 4             | MOGUL AREA  | 1325              | 1350             | 25            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/3/2004 | 4             | MOGUL AREA  | 1350              | 1415             | 25            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/3/2004 | 4             | MOGUL AREA  | 1415              | 1430             | 15            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/3/2004 | 4             | MOGUL AREA  | 1430              | 1445             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/3/2004 | 4             | MOGUL AREA  | 1445              | 1455             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/3/2004 | 4             | MOGUL AREA  | 1455              | 1505             | 10            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/3/2004 | 4             | MOGUL AREA  | 1505              | 1515             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/3/2004 | 4             | MOGUL AREA  | 1515              | 1530             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/3/2004 | 4             | MOGUL AREA  | 1530              | 1550             | 20            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |
| 6/3/2004 | 4             | MOGUL AREA  | 1550              | 1615             | 25            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | SUNNY MUDDY      |

| Date     | No. of People | Area Tested     | Status Start Time | Status Stop Time | Duration, min | Operational Status | OP Stat Code | Operational Status - Comments | Track Method | Track Method=Other Explain | Pattern | Field Conditions |       |
|----------|---------------|-----------------|-------------------|------------------|---------------|--------------------|--------------|-------------------------------|--------------|----------------------------|---------|------------------|-------|
| 6/3/2004 | 4             | MOGUL AREA      | 1615              | 1645             | 30            | DAILY START/STOP   | 3            | END OF DAILY OPERATIONS       | GPS          | NA                         | LINEAR  | SUNNY            | MUDGY |
| 6/4/2004 | 4             | BLIND TEST GRID | 1000              | 1010             | 10            | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY           | MUDGY |
| 6/4/2004 | 4             | BLIND TEST GRID | 1010              | 1025             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY           | MUDGY |
| 6/4/2004 | 4             | BLIND TEST GRID | 1025              | 1030             | 5             | DAILY START/STOP   | 3            | SET UP, MOVE CABLES           | GPS          | NA                         | LINEAR  | CLOUDY           | MUDGY |
| 6/4/2004 | 4             | BLIND TEST GRID | 1030              | 1045             | 15            | COLLECT DATA       | 4            | COLLECT DATA                  | GPS          | NA                         | LINEAR  | CLOUDY           | MUDGY |
| 6/4/2004 | 4             | BLIND TEST GRID | 1045              | 1110             | 25            | LUNCH/BREAK        | 5            | LUNCH/BREAK                   | GPS          | NA                         | LINEAR  | CLOUDY           | MUDGY |
| 6/4/2004 | 4             | BLIND TEST GRID | 1110              | 1215             | 75            | DEMOBILIZATION     | 10           | DEMOBILIZATION                | GPS          | NA                         | LINEAR  | CLOUDY           | MUDGY |
| 6/4/2004 | 4             | BLIND TEST GRID | 1215              | 1315             | 60            | LUNCH/BREAK        | 5            | LUNCH/BREAK                   | GPS          | NA                         | LINEAR  | CLOUDY           | MUDGY |
| 6/4/2004 | 4             | BLIND TEST GRID | 1315              | 1530             | 135           | DEMOBILIZATION     | 10           | DEMOBILIZATION                | GPS          | NA                         | LINEAR  | CLOUDY           | MUDGY |

Note: Activities pertinent to this specific demonstration are indicated in highlighted text.

## **APPENDIX E. REFERENCES**

1. Standardized UXO Technology Demonstration Site Handbook, DTC Project No. 8-CO-160-000-473, Report No. ATC-8349, March 2002.
2. Aberdeen Proving Ground Soil Survey Report, October 1998.
3. Data Summary, UXO Standardized Test Site: APG Soils Description, May 2002.
4. Yuma Proving Ground Soil Survey Report, May 2003.

## APPENDIX F. ABBREVIATIONS

|       |   |  |
|-------|---|--|
| AEC   | = | U.S. Army Environmental Center   |
| APG   | = | Aberdeen Proving Ground  |
| ATC   | = | U.S. Army Aberdeen Test Center   |
| CSV   | = | comma separated values   |
| DGPS  | = | Digital Global Positioning System  |
| EM    | = | electromagnetic  |
| EMI   | = | electromagnetic interference   |
| ERDC  | = | U.S. Army Corps of Engineers Engineering Research and Development Center |
| ESTCP | = | Environmental Security Technology Certification Program                  |
| EQT   | = | Army Environmental Quality Technology Program                            |
| GPS   | = | Global Positioning System  |
| HEAT  | = | high-explosive, antitank   |
| JPG   | = | Jefferson Proving Ground   |
| POC   | = | point of contact   |
| QA    | = | quality assurance  |
| QC    | = | quality control  |
| RMS   | = | root-mean-square   |
| ROC   | = | receiver-operating characteristic  |
| RTS   | = | Robotic Total Station  |
| SAM   | = | Sub-Audio Magnetics  |
| SERDP | = | Strategic Environmental Research and Development Program                 |
| TFEMI | = | Total Field Electromagnetic Introduction                                 |
| TMI   | = | Total Magnetic Intensity   |
| UXO   | = | unexploded ordnance  |
| YPG   | = | U.S. Army Yuma Proving Ground  |

## APPENDIX G. DISTRIBUTION LIST

DTC Project No. 8-CO-160-UXO-021

| <u>Addressee</u>  | <u>No. of Copies</u> |
|---|----------------------|
| Commander<br>U.S. Army Environmental Center<br>ATTN: SFIM-AEC-ATT (Mr. George Robitaille)<br>Aberdeen Proving Ground, MD 21010-5401                               | 2                    |
| Geophysical Technology Limited (G-TEK)<br>ATTN: (Dr. John M. Stanley)<br>Unit 3, No. 10, Hudson Road<br>Albion, Australia 4010                                    | 1                    |
| SERDP/ESTCP<br>ATTN: (Ms. Anne Andrews)<br>901 North Stuart Street, Suite 303<br>Arlington, VA 22203  | 1                    |
| Commander<br>U.S. Army Aberdeen Test Center<br>ATTN: CSTE-DTC-SL-E (Mr. Larry Overbay)<br>(Library)<br>CSTE-DTC-AT-CS-R<br>Aberdeen Proving Ground, MD 21005-5059 | 1<br>1<br>1          |
| Defense Technical Information Center<br>8725 John J. Kingman Road, STE 0944<br>Fort Belvoir, VA 22060-6218  | 2                    |

Secondary distribution is controlled by Commander, U.S. Army Environmental Center,  
ATTN: SFIM-AEC-ATT.